

F.A.U. ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8047	96-00379-00-PV	SANG	66	2
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	354
20200100	EARTH EXCAVATION	CU YD	15,506
20800150	TRENCH BACKFILL	CU YD	2,003
25000200	SEEDING, CLASS 2	ACRE	2.0
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	180
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	180
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	180
25000700	AGRICULTURAL GROUND LIMESTONE	TON	4
25100125	MULCH, METHOD 3	ACRE	2.0
25100630	EROSION CONTROL BLANKET	SQ YD	531.0
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	600
28000300	TEMPORARY DITCH CHECKS	EACH	43
28000400	PERIMETER EROSION BARRIER	FOOT	6,288
28000500	INLET AND PIPE PROTECTION	EACH	102
28100105	STONE RIPRAP, CLASS A3	SQ YD	87
28200200	FILTER FABRIC	SQ YD	87
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	22,547
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	1,500
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	87
40600990	TEMPORARY RAMP	SQ YD	141
40701881	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10"	SQ YD	20,456
40800050 *	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	9
42001300	PROTECTIVE COAT	SQ YD	4,031
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	261
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	30,916

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
42400800	DETECTABLE WARNINGS	SQ FT	204
44000400	GUTTER REMOVAL	FOOT	433
44000100	PAVEMENT REMOVAL	SQ YD	2,141
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	184
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	205
44000600	SIDEWALK REMOVAL	SQ FT	469
44201729	CLASS D PATCHES, TYPE II, 7 INCH	SQ YD	7
44201733	CLASS D PATCHES, TYPE III, 7 INCH	SQ YD	21
44201735	CLASS D PATCHES, TYPE IV, 7 INCH	SQ YD	33
50105220	PIPE CULVERT REMOVAL	FOOT	582
54010302 *	PRECAST CONCRETE BOX CULVERT 3' X 2'	FOOT	435
54010402 *	PRECAST CONCRETE BOX CULVERT 4' X 2'	FOOT	133
54010503 *	PRECAST CONCRETE BOX CULVERT 5' X 3'	FOOT	388
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	5
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	3
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2
55100300	STORM SEWER REMOVAL 8"	FOOT	55
55100500	STORM SEWER REMOVAL 12"	FOOT	314
55100700	STORM SEWER REMOVAL 15"	FOOT	53
55100900	STORM SEWER REMOVAL 18"	FOOT	55
55034300	STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 30, RISE 19	FOOT	154
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	149
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	8
60218500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	3

* - SEE SPECIAL PROVISIONS

NOTE: ALL ITEMS ARE UNDER CONSTRUCTION TYPE CODE 1000-2A

SUMMARY OF QUANTITIES
ILES AVENUE SECTION 96-00379-00-PV
SHEET 2 OF 66 SHEETS