

F.A.U. ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8047	96-00379-00-PV	SANG	66	3
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5
60221200	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	2
60221700	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	1
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1
60228600 *	MANHOLES, SPECIAL WITH TYPE 1 FRAME, CLOSED LID	EACH	11
60228700 *	MANHOLES, SPECIAL WITH TYPE 3 FRAME AND GRATE	EACH	1
60228900 *	MANHOLES, SPECIAL WITH TYPE 8 GRATE	EACH	1
60235300	INLETS, TYPE A, TYPE 1 FRAME, CLOSED LID	EACH	1
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	42
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	11
60237000	INLETS, TYPE A, TYPE 15 FRAME AND LID	EACH	3
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	1
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	1
60266600	VALVE BOXES TO BE ADJUSTED	EACH	7
60500040 *	REMOVING MANHOLES	EACH	1
60500060 *	REMOVING INLETS	EACH	2
60602200	CONCRETE GUTTER	FOOT	32
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	6,242
60801008	FLAP GATE 8"	EACH	1
66700105	PERMANENT SURVEY MARKERS (SPECIAL)	EACH	1
67100100	MOBILIZATION	L SUM	1
70103700 *	TRAFFIC CONTROL COMPLETE	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	900
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	355

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	13,980
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	839
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,500
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	120
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	8,640
72000100	SIGN PANEL - TYPE 1	SQ FT	20
72900110	METAL POST - TYPE A	EACH	3
78000100 Δ	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	338
78000300 Δ	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	12,649
78000400 Δ	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	839
78000600 Δ	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	214
78000650 Δ	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	120
78001100 Δ	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	17
78001120 Δ	PAINT PAVEMENT MARKING - LINE 5"	FOOT	1,331
78001150 Δ	PAINT PAVEMENT MARKING - LINE 12"	FOOT	1,286
78300100	PAVEMENT MARKING REMOVAL	SQ FT	90
XX000856 *	MAILBOX REMOVAL AND RELOCATION	EACH	7
XX004895 *	PIPE UNDERDRAIN CLEANOUT, COMPLETE	EACH	1
X0321556 *	SANITARY MANHOLES TO BE ADJUSTED	EACH	10
X0322124 *	STORM SEWER (WATER MAIN REQUIREMENTS) 8 INCH	FOOT	17
X0322033 *	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	1,516
X0322034 *	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	52
X0322035 *	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	947
X0322127 *	STORM SEWER (WATER MAIN REQUIREMENTS) 30 INCH	FOOT	610
Z0013798 *	CONSTRUCTION LAYOUT	L SUM	1
+ Z0076600*	TRAINEES	HOUR	1000

Δ - SPECIALTY ITEMS
 * - SEE SPECIAL PROVISIONS
 + - Y080
 NOTE: ALL ITEMS ARE UNDER CONSTRUCTION TYPE CODE 1000 -2A

SUMMARY OF QUANTITIES
 ILES AVENUE SECTION 96-00379-00-PV
 SHEET 3 OF 66 SHEETS