

F.A.U. ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8047	96-00379-00-PV	SANG	66	8
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

STORM SEWER REMOVAL

STATION TO STATION	SIDE	STORM SEWER REM 8	STORM SEWER REM 12	STORM SEWER REM 15	STORM SEWER REM 18	TRENCH BACKFILL	
FOOT						CU. YD.	
464+06	466+26	RT		220.0		97.8	
480+64	481+19	LT			55.0	14.3	
484+27	484+57			31.0		8.6	
485+17		LT/RT	55			10.2	
487+89	488+51	RT		63.0		28.0	
489+32		LT/RT			53.0	22.3	
TOTAL			55.0	314.0	53.0	55.0	181.2
USE			55	314	53	55	182

CULVERT REMOVAL

STATION TO STATION	SIDE	SIZE	TYPE	FOOT	TRENCH BACKFILL	
FOOT					CU. YD.	
458+86.42	LT/RT	30"	RCCP	52.0	22.4	
459+03.36	460+23.14	RT	24"	RCCP	120.0	63.1
463+31.16		RT	24"	RCCP	12.4	2.7
473+40.38		LT	12"	RCCP	14.0	0.0
473+81	474+82	LT	24"	CMP	104.0	38.5
475+29	475+58	LT	10"	STEEL	33.0	4.6
478+35	478+54	LT	8"	CMP	20.0	1.7
479+39	479+59	LT	10"	CMP	20.0	1.9
482+85	483+05	LT	12"	CMP	19.0	2.6
483+74	484+05	LT	12"	CMP	31.0	4.3
485+80	486+05	LT	12"	CMP	24.0	4.4
486+31		LT/RT	12"	CMP	35.0	6.5
486+33		LT/RT	12"	CMP	35.0	6.5
486+42	486+78	RT	24"	CMP	37.0	11.0
490+37	490+62	LT	12"	CMP	25.0	3.5
TOTAL				581.4	173.5	
USE				582	174	

TRENCH BACKFILL

TRENCH BACKFILL	CU. YDS
STORM SEWER	1,647
PIPE CULVERT REMOVAL	174
STORM SEWER REMOVAL	182
TOTAL	2003

PATCHING SCHEDULE

STATIONS	SIDE	CLASS D PATCHES, TYPE II 7 INCH	CLASS D PATCHES, TYPE III 7 INCH	CLASS D PATCHES, TYPE IV 7 INCH
459+40.47 - 459+69.17	LT	7.0		
458+83.16 - 458+94.45	LT / RT		20.4	
459+32.99 - 459+95.85	RT			33.0
TOTAL		7.0	20.4	33.0
USE		7	21	33

PAVEMENT SCHEDULE

STATION TO STATION	SUB GRAN MAT A 12	HMA SURF REM BUTT JT	PAVEMENT REM	TEMPORARY RAMP	HMA PAVT FD 10	INCIDENTAL HMA SURF	
	SQ YD		SQ YD			TON	
ILES AVENUE							
460+29.49	460+49.49		29.2			6.5	
460+49.49	491+90.00	22,546.9			20,456.3		
465+16	RT		676.5	27.0			
474+30	LT		221.1	16.9			
478+26	RT		239.7	18.6			
480+92	LT		137.3	14.9			
488+19	LT		166.9	18.8			
488+20	RT		199.6	15.0			
491+90.00	492+00.00		57.8	499.2	28.9	2.4	
TOTAL		22,546.9	87.0	2140.3	140.1	20,456.3	8.9
USE		22,547	87	2,141	141	20,456	9

CURB REMOVAL AND REPLACEMENT

STATION TO STATION	SIDE	GUTTER REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	CONCRETE GUTTER	COMB CC&G TB6.18	
FOOT						
459+38	459+42.15	LT		3.9	3.9	
460+44.49	474+15.57	LT			1385.3	
460+49.49	464+78.30	RT			458.7	
464+20	464+78	RT		94.9		
465+55	466+14	RT		93.7		
465+54.58	478+10.17	RT			1301.5	
474+42.96	480+78.82	LT			667.0	
477+83	478+10	RT	71.9			
478+44	478+72	RT	73.3			
478+44.33	487+95.77	RT			966.2	
487+95.77	488+05.92	RT		22.8		
480+65	480+78	LT	34.1			
481+06	481+17	LT	33.9			
481+05.68	488+02.45	LT			730.1	
487+77	488+02	LT	55.7			
488+36	488+54	LT	29.5			
487+80	488+06	RT	78.0			
488+33	488+61	RT	56.4			
488+32.89	488+35.92	RT		8.5		
488+43.04	491+95	RT			351.8	
488+36.32	491+90	LT			376.6	
491+89	491+95	RT		6.6		
491+90	491+95	LT		5.1		
TOTAL			432.6	204.1	31.3	6241.2
USE			433	205	32	6242

STORM SEWER REMOVAL

STATION	SIDE	REMOVING MANHOLES	REMOVING INLETS
EACH			
485+17	LT		1
485+17	RT		1
489+32	LT	1	
TOTALS		1	2