

FAU	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7998	97-00030-06-WR	SANGAMON	117	3
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

ITEM NO.	DESCRIPTION	UNIT	ROADWAY QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	474
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	650
20100500	TREE REMOVAL, ACRES	ACRE	0.7
20200100	EARTH EXCAVATION	CU YD	22,982
20800150	TRENCH BACKFILL	CU YD	1,258
25000200	SEEDING, CLASS 2	ACRE	8
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	720
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	720
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	720
25000700	AGRICULTURAL GROUND LIMESTONE	TON	16
25100120	MULCH, METHOD 2	TON	16
25200100	SODDING	SQ YD	12
25200200	SUPPLEMENTAL WATERING	UNIT	0.1
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2,373
28000300	TEMPORARY DITCH CHECKS	EACH	56
28000400	PERIMETER EROSION BARRIER	FOOT	7,044
28000500	INLET AND PIPE PROTECTION	EACH	16
28100725	STONE DUMPED RIPRAP, CLASS B3	SQ YD	6
28100830	STONE DUMPED RIPRAP, CLASS B4	TON	31
28200200	FILTER FABRIC	SQ YD	37
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	34,530
30201500	LIME	TON	691
35100300	AGGREGATE BASE COURSE, TYPE A 4"	SQ YD	470
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	2,917
35650300	BASE COURSE WIDENING 8"	SQ YD	350
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	18,371
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	452
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	211
40600990	TEMPORARY RAMP	SQ YD	44
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	343
40701901	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 11"	SQ YD	30,279
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	457
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	3,554
44000100	PAVEMENT REMOVAL	SQ YD	17,564
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	3,693
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,953
44000300	CURB REMOVAL	FOOT	63
44000400	GUTTER REMOVAL	FOOT	384
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	6
44000600	SIDEWALK REMOVAL	SQ FT	68
44004250	PAVED SHOULDER REMOVAL	SQ YD	3,514
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1,639
48101200	AGGREGATE SHOULDERS, TYPE B	TON	148
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	1,374
48203100	HOT-MIX ASPHALT SHOULDERS	TON	39
50105220	PIPE CULVERT REMOVAL	FOOT	1,348
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	5
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	5
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	3
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	4
54214527	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 42"	EACH	4

CONSTRUCTION TYPE CODE: 1000  
 • SEE SPECIAL PROVISION  
 < DENOTES "SPECIALTY ITEM"

<b>ie</b> consultants	IE CONSULTANTS, INC. 6420 SOUTH SIXTH STREET SPRINGFIELD, ILLINOIS 62712 TEL. (217) 529-8027 FAX (217) 529-4549 IESPRINGFIELD@IE-CONSULTANTS.COM WWW.IE-CONSULTANTS.COM
	<b>SUMMARY OF QUANTITIES</b>

DESIGNED BY: JEB	DRAWN BY: AAD	CHECKED BY: CMS	DATE: 4/4/08
---------------------	------------------	--------------------	-----------------