

| | | | | |
|---------------------|----------------|---------------------------|--------------|-----------|
| FAU | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 7998 | 97-00030-06-WR | SANGAMON | 117 | 4 |
| FED. ROAD DIST. NO. | | ILLINOIS FED. AID PROJECT | | |

| ITEM NO. | DESCRIPTION | UNIT | ROADWAY QUANTITY |
|----------|---|-------|------------------|
| 542A0220 | PIPE CULVERTS, CLASS A, TYPE 1 15" | FOOT | 68 |
| 542A0229 | PIPE CULVERTS, CLASS A, TYPE 1 24" | FOOT | 84 |
| 542A1075 | PIPE CULVERTS, CLASS A, TYPE 2 30" | FOOT | 120 |
| 542A5497 | PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 42" | FOOT | 192 |
| 550A0050 | STORM SEWERS, CLASS A, TYPE 1 12" | FOOT | 1,951 |
| 550A0070 | STORM SEWERS, CLASS A, TYPE 1 15" | FOOT | 276 |
| 550A0090 | STORM SEWERS, CLASS A, TYPE 1 18" | FOOT | 230 |
| 550A0140 | STORM SEWERS, CLASS A, TYPE 1 30" | FOOT | 143 |
| 550A0340 | STORM SEWERS, CLASS A, TYPE 2 12" | FOOT | 431 |
| 550A0360 | STORM SEWERS, CLASS A, TYPE 2 15" | FOOT | 315 |
| 550A0410 | STORM SEWERS, CLASS A, TYPE 2 24" | FOOT | 102 |
| 55100500 | STORM SEWER REMOVAL 12" | FOOT | 278 |
| 55100700 | STORM SEWER REMOVAL 15" | FOOT | 405 |
| 55101100 | STORM SEWER REMOVAL 21" | FOOT | 56 |
| 60207605 | CATCH BASINS, TYPE C, TYPE 8 GRATE | EACH | 3 |
| 60224600 | RESTRICTED DEPTH MANHOLES, 4' -DIAMETER, TYPE 1 FRAME, CLOSED LID | EACH | 4 |
| 60255500 | MANHOLES TO BE ADJUSTED | EACH | 5 |
| 60255905 | MANHOLES TO BE ADJUSTED WITH NEW TYPE 3V FRAME AND GRATE | EACH | 3 |
| 60260100 | INLETS TO BE ADJUSTED | EACH | 1 |
| 60265700 | VALVE VAULTS TO BE ADJUSTED | EACH | 2 |
| 60500040 | REMOVING MANHOLES | EACH | 1 |
| 60500060 | REMOVING INLETS | EACH | 2 |
| 60600097 | CLASS SI CONCRETE (OUTLET), SPECIAL | CU YD | 5 |
| 60600605 | CONCRETE CURB, TYPE B | FOOT | 30 |
| 60605000 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 | FOOT | 11,656 |
| 63301210 | REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A | FOOT | 25 |
| 67100100 | MOBILIZATION | L SUM | 1 |
| 70100450 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701201 | L SUM | 1 |
| 70100460 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701306 | L SUM | 1 |
| 70100500 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701326 | L SUM | 1 |
| 70101800 | TRAFFIC CONTROL AND PROTECTION, (SPECIAL) | L SUM | 1 |
| 70102620 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701501 | L SUM | 1 |
| 70102622 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701502 | L SUM | 1 |
| 70102640 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701801 | L SUM | 1 |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 4,057 |
| 70300210 | TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 2,075 |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 91,698 |
| 70300230 | TEMPORARY PAVEMENT MARKING - LINE 5" | FOOT | 39,459 |
| 70300240 | TEMPORARY PAVEMENT MARKING - LINE 6" | FOOT | 5,364 |
| 70300260 | TEMPORARY PAVEMENT MARKING - LINE 12" | FOOT | 2,268 |
| 70300280 | TEMPORARY PAVEMENT MARKING - LINE 24" | FOOT | 351 |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 1,352 |
| 72000200 | SIGN PANEL - TYPE 2 | SQ FT | 77.5 |
| 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 16,850 |
| 78000300 | THERMOPLASTIC PAVEMENT MARKING - LINE 5" | FOOT | 10,607 |
| 78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 1,565 |
| 78000600 | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | FOOT | 377 |
| 78004200 | PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS | SQ FT | 780 |
| 78004230 | PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6" | FOOT | 349 |
| 78004280 | PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24" | FOOT | 202 |
| 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 359 |
| 80500100 | SERVICE INSTALLATION, TYPE A | EACH | 1 |

CONSTRUCTION TYPE CODE: 1000
 • SEE SPECIAL PROVISION
 < DENOTES "SPECIALTY ITEM"

| | | | |
|---|--|--|--|
|  | IE CONSULTANTS, INC. 6420 SOUTH SIXTH STREET SPRINGFIELD, ILLINOIS 62712 TEL: (217) 529-8027 FAX: (217) 529-4543 IESPRINGFIELD@IE-CONSULTANTS.COM WWW.IE-CONSULTANTS.COM | | |
| | SUMMARY OF QUANTITIES | | |

| | | | |
|--------------|-----------|-------------|--------|
| DESIGNED BY: | DRAWN BY: | CHECKED BY: | DATE: |
| JEB | AAD | CMS | 4/4/08 |