

FAU	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7998	97-00030-06-WR	SANGAMON	117	9
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SCHEDULE OF QUANTITIES

STRIPING SCHEDULE																		
LOCATION	THERMOPLASTIC PAVEMENT MARKING - LINE 4"			THERMOPLASTIC PAVEMENT MARKING - LINE 5"	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B, INLAID - LINE 6"	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B, INLAID - LINE 24"	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B, INLAID - LETTERS AND SYMBOLS	RAISED REFLECTIVE PAVEMENT MARKER	SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING, LETTERS & SYMBOLS	TEMPORARY PAVEMENT MARKING					WORK ZONE PAVEMENT MARKING REMOVAL
	SOLID YELLOW	SKIP-DASH YELLOW	DOUBLE YELLOW	SOLID WHITE	SOLID WHITE	DOTTED WHITE	YELLOW	WHITE	WHITE	(EACH)	(FOOT)	(SQ FT)	4"	5"	6"	12"	24"	(SQ FT)
	(FOOT)			(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(SQ FT)	(EACH)	(FOOT)	(SQ FT)	(FOOT)					(SQ FT)
EAST LAKE SHORE DRIVE																		
9+00 TO 12+67			680	748	90	36			31.2	21	110	93.6	1,440	762	372			37
12+67 TO 21+23	580	145	585	1640	185	50	50		93.6	45	500	280.8	6,345	5,139	705	240		167
21+23 TO 29+64	760	190	1290	1626	245	50	50		93.6	45	490	280.8	6,270	5,052	705	240		163
29+64 TO 42+37	1582	396	1170	2510	185	50	50	26	156.0	65	740	468	9,354	7,638	705	240		248
42+37 TO 56+50	1882	470	1174	2709	400	85	55	38	249.6	76	880	561.6	10,245	8,478	1,287	240		293
56+50 TO 67+50			2962	746	200	39	112	43	46.8	57	580	93.6	9,342	6,600	705	540		193
ROCHESTER ROAD																		
98+74 TO 99+88			150	245				18			58		801				54	19
100+00 TO 109+95			2654	1987	200	39	60	32	93.6	50	592	249.6	9,378	5,790	705	672	96	197
BRITTANY LANE																		
300+40 TO 300+65			60	70				17			27		198				51	9
LACONWOOD DRIVE																		
400+40 TO 401+01			120	121	60			28	15.6		58	46.8	360		180		84	19
BUCKEYE DRIVE																		
500+40 TO 500+90				105				26			22					96	66	7
STAGE 1																		
EAST LAKE SHORE DRIVE																		
9+00 TO 12+67													835					
12+67 TO 21+23													1,932					
21+23 TO 29+64													1,903					
29+64 TO 42+37													2,865					
42+37 TO 56+50													3,185					
56+50 TO 67+50													2,480					
ROCHESTER ROAD																		
98+74 TO 99+88													3,860					
100+00 TO 109+95																		
SUB-TOTALS	4,804	1,201	10,845	10,607	1,565	349	377	202	780.0	359	4,057	2,075	70,793	39,459	5,364	2,268	351	1,352

IE CONSULTANTS, INC.
6420 SOUTH SIXTH STREET
SPRINGFIELD, ILLINOIS 62712
TEL. (217) 529-8027
FAX (217) 529-4543
IESPRINGFIELD@IE-CONSULTANTS.COM
WWW.IE-CONSULTANTS.COM

SCHEDULE OF QUANTITIES

DESIGNED BY: JEB	DRAWN BY: AAD	CHECKED BY: CMS	DATE: 4/4/08
---------------------	------------------	--------------------	-----------------

4/9/2008