

FAU	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7998	97-00030-06-WR	SANGAMON	117	11
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SCHEDULE OF QUANTITIES

EROSION CONTROL SCHEDULE							
STATION	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	INLET & PIPE PROTECTION	STONE DUMPED RIPRAP CLASS B3	STONE DUMPED RIPRAP CLASS B4	FILTER FABRIC	REMOVE EXISTING RIPRAP
	(EACH)	(FOOT)	(EACH)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)
EAST LAKE SHORE DRIVE							
STA. 9+10 TO STA. 12+70, LT.		427					
STA. 9+53, RT.					10	10	10
STA. 9+53 TO STA. 10+95, RT.		166					
STA. 10+03, RT.			1				
STA. 11+28 TO STA. 14+00, RT.		270					
STA. 12+90 TO STA. 14+50, LT.		230					
STA. 14+50 TO STA. 15+12, LT.		62					
STA. 17+10 TO STA. 20+00, LT.		297					
STA. 17+20, LT.			1				
STA. 18+50 TO STA. 19+50, RT.		96					
STA. 20+00 TO STA. 21+00, LT.		114					
STA. 21+45 TO STA. 25+50, RT.		410					
STA. 24+77 TO STA. 25+50, LT.		73					
STA. 25+50 TO STA. 27+20, LT.		172					
STA. 25+50 TO STA. 25+93, RT.		43					
STA. 28+00, LT.	1						
STA. 28+00 TO STA. 29+00, RT.		101					
STA. 29+00, LT.			1				
STA. 30+00 TO STA. 31+00, LT.		146					
STA. 30+50, LT.			1				
STA. 31+00 TO STA. 36+70, LT.		578					
STA. 32+00, LT.	1						
STA. 33+70, LT.	1						
STA. 35+40, LT.	1						
STA. 35+00, RT.	1						
STA. 35+70, RT.			1				
STA. 36+70 TO STA. 41+20, RT.		450					
STA. 36+80, LT.	1						
STA. 36+90, RT.	1						
STA. 37+07, LT.			1				
STA. 37+07, RT.	1						
STA. 37+30, RT.	1						
STA. 38+50 TO STA. 42+00, LT.		370					
STA. 39+10, LT.	1						
STA. 39+25, LT.			1				
STA. 39+25, RT.	1						
STA. 39+40, LT.	1						

EROSION CONTROL SCHEDULE							
STATION	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	INLET & PIPE PROTECTION	STONE DUMPED RIPRAP CLASS B3	STONE DUMPED RIPRAP CLASS B4	FILTER FABRIC	REMOVE EXISTING RIPRAP
	(EACH)	(FOOT)	(EACH)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)
EAST LAKE SHORE DRIVE							
STA. 40+00, LT.	1						
STA. 40+60, LT.	1						
STA. 41+00, RT.			1				
STA. 41+50, LT.	1						
STA. 42+50 TO STA. 45+00, LT.		248					
STA. 43+60, LT.	1						
STA. 44+40, LT.	1						
STA. 44+40, RT.	1						
STA. 45+10, LT.	1						
STA. 46+00, LT.	1						
STA. 46+30, LT.	1						
STA. 46+40, LT.			1				
STA. 46+90, RT.	1						
STA. 47+00, RT.	1						
STA. 47+10, RT.	1						
STA. 47+45, LT.	1						
STA. 48+80 TO STA. 51+20, LT.		256					
STA. 50+00, LT.	1						
STA. 50+25 TO STA. 52+00, RT.		212					
STA. 50+50, LT.	1						
STA. 50+55, LT.			1				
STA. 50+80, LT.	1						
STA. 51+50, LT.	1						
STA. 53+00 TO STA. 55+75, RT.		350					
STA. 54+80 TO STA. 56+00, LT.		157					
STA. 56+12, LT.			1				
STA. 57+00, LT.	1						
STA. 57+17, LT.				3		3	
STA. 57+75, RT.	1						
STA. 58+10, LT.	1						

ie consultants
 IE CONSULTANTS, INC.
 6420 SOUTH SIXTH STREET
 SPRINGFIELD, ILLINOIS 62712
 TEL. (217) 529-8027
 FAX (217) 529-4543
 IESPRINGFIELD@IE-CONSULTANTS.COM
 WWW.IE-CONSULTANTS.COM

SCHEDULE OF QUANTITIES

DESIGNED BY: JEB	DRAWN BY: AAD	CHECKED BY: CMS	DATE: 4/4/08
---------------------	------------------	--------------------	-----------------

4/5/2008