93467

FAU	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7998	97-00030-06-WR	SANGAMON	117	15
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

PIPE & STRUCTURE NUMBERS	PIPE LOCATION	STANDARD NUMBER	TRENCH BACKFILL CU. YD.	STORM SEWERS FOOT CLASS A TYPE 1 12"	15"	18"	30"	TYPE 2 12"	15"	24"	30"	PIPE CULVERTS FOOT CLASS A TYPE 1 15"	24"	TYPE 2 30"	PIPE CULVERTS FOOT CLASS A TYPE 1 EQRS 42"	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	15"	18"	24"	30"	EQRS 42"	INLETS TYPE A TYPE 3V F & G	CATCH BASIN TYPE C TYPE B GRATE	RD CATCH BASIN 3' DIA. TYPE 3V F & G	RD MANHOLES 4' DIA TYPE 3V F & G	RD MANHOLES 5' DIA TYPE 3V F & G	RD MANHOLES 4' DIA TYPE 1 FRAME CLID	INLETS TO BE ADJUSTED	REMOVING MANHOLES	MANHOLES TO BE ADJUSTED	MANHOLES TO BE ADJUSTED WITH NEW TYPE 3V F & G	REMOVE & RE-INSTALL CONCRETE FLARED END SECTIONS
P-65	S-77 TO S-76			15																											
S-77	STA. 49+00, RT																					1									
S-78	STA. 50+30, RT																					1									
P-66	S-78 TO S-79							2																							
S-79	STA. 50+30, RT																										1				
S-81	STA. 50+55, LT																		1												
P-67	S-81 TO S-80									102																					
S-80	STA. 51+04, RT																													1	
S-82	STA. 51+80, RT																					1									
P-68	S-82 TO S-83							4																							
S-83	STA. 51+80, RT																										1				
S-84	STA. 54+50, LT																					1									
P-72	S-84 TO S-85			118																											
S-85	STA. 55+70, LT																							1							
P-73	S-85 TO S-86				26																										
S-86	STA. 55+90, LT																1														
C-1	STA. 56+12, LT												84						2												
S-87	STA. 57+70, LT																					1									
P-75	S-87 TO S-88			22																											
S-88	STA. 57+70, LT																														1
S-90	STA. 59+50, LT																					1									
P-80	S-90 TO S-91			22																											
S-91	STA. 59+50, LT															1															
S-92	STA. 60+90, LT																					1									
P-81	S-92 TO S-93			22																											
S-93	STA. 60+90, LT															1															
C-2	STA. 61+00														192						4										
S-95	STA. 61+87, LT																					1									
P-82	S-95 TO S-96							15																							
S-96	STA. 62+02, LT																								1						
P-84	S-96 TO S-94							60																							
S-94	STA. 62+02, RT																														1
P-83	S-97 TO S-96							48																							
S-97	STA. 62+50, LT																					1									
C-3	STA. 63+02													120						2											
S-98	STA. 64+50, RT																					1									
P-91	S-98 TO S-99							24																							
S-99	STA. 64+50, RT																							1							
P-90	S-99 TO S-100							36																							
S-100	STA. 64+50, RT															1															
C-4	STA. 103+87											34					2														
C-5	STA. 105+28											34					2														
TOTALS				1,951	276	230	143	431	315	102	0	68	84	120	192	5	5	1	3	4	4	21	3	22	2	3	4	1	1	2	3	3

ie consultants

IE CONSULTANTS, INC.
6420 SOUTH SIXTH STREET
SPRINGFIELD, ILLINOIS 62712
TEL. (217) 529-8027
FAX (217) 529-4643
IESPRINGFIELD@IE-CONSULTANTS.COM
WWW.IE-CONSULTANTS.COM

SCHEDULE OF QUANTITIES

DESIGNED BY:	DRAWN BY:	CHECKED BY:	DATE:
JEB	AAD	CMS	4/4/08

4/18/2008

g:\S842\CAD\Roadway\842sch10.dgn