

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	1YRS, 2ZRS-1	CRAWFORD	378	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

CODE NO.	ITEMS	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE TYPE							
				L24		L24		L20			
				80% FED	20% STATE	80% FED	20% STATE	80% FED	20% STATE	100% CITY	50% STATE
				F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)		
				0+915.000 TO 2+756.900 AND 4+475.071 TO 15+545.000	2+756.900 TO 4+475.071	15+545.000 TO 16+016.000	2+756.900 TO 4+475.071	2+756.900 TO 4+475.071	2+756.900 TO 4+475.071		
				I000-2A RURAL	I000-2A RURAL	I000-2A URBAN	SFTY-1B URBAN	SFTY-1B URBAN	SFTY-1B URBAN		
M7040200	RELOCATE TEMPORARY CONCRETE BARRIER	METER	1430		1330		100				
** M7800205	PAINT PAVEMENT MARKING LINE-100 MM	METER	33577		32091		426		1060		
** M7800215	PAINT PAVEMENT MARKING LINE-150 MM	METER	106.8				106.8				
** M7800240	PAINT PAVEMENT MARKING LINE-600 MM	METER	15.6				15.6				
* MX032188	CLASS SI CONCRETE, SPECIAL	CU M	15.0				15.0				
* MX032196	POLYMER MODIFIED PORTLAND CEMENT MORTAR	SQ M	25.9		25.9						
* MX032200	ENGINEERED BARRIER	SQ M	457				457				
* MX032509	GRADING AND SHAPING SPECIAL	SQ M	9815				9815				
* M2112500	TOPSOIL EXCAVATION AND PLACEMENT	CU M	24190		23434.0		9.7		741.7		
MX033694	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 125 MM)	SQ M	3.2		3.2						
MX540110	PRECAST CONCRETE BOX CULVERT 1.5M x 0.6M	METER	64.4				64.4				
MX033731	PRECAST CONCRETE BOX CULVERT 900MM x 450MM	METER	15.2		15.2						
MX033735	PRECAST CONCRETE BOX CULVERT 3.0M x 0.9M	METER	43.2		43.2						
MX033732	PRECAST CONCRETE BOX CULVERT 3.0M x 1.65M	METER	10.9		10.9						
MX033736	PRECAST CONCRETE BOX CULVERT 750MM x 450MM (M273)	METER	51.0		36.6				14.4		
MX033737	PRECAST CONCRETE BOX CULVERT 900MM x 300MM (M273)	METER	29.7		29.7						
MX033734	PRECAST CONCRETE BOX CULVERT 1.8M x 0.6M (M273)	METER	15.3		15.3						
* MZ034730	MODULAR RETAINING WALL SYSTEM	SQ M	97.1				97.1				
* Z0007601	BUILDING REMOVAL NO. 1	L SUM	1		1						
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4		4						
Z0030350	IMPACT ATTENUATOR, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	15		13				2		
** A2001016	TREE, ACER RUBRUM (RED MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	40		30		5		5		
** A2006416	TREE, QUERCUS ALBA (WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	40		30		5		5		
** D2002788	EVERGREEN, PICEA PUNGENS GLAUCA (COLORADO BLUE SPRUCE), 8' HEIGHT, BALLED AND BURLAPPED	EACH	15						15		
** A2001316	TREE, ACER SACCHARINUM (SILVER MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	35		30		5				
** A2006916	TREE, QUERCUS PALUSTRIS (PIN OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	40		30		5		5		
0 Z0076600	TRAINEES	HOUR	1000		1000						

- \* SEE SPECIAL PROVISIONS
- \*\* Specialty Items
- 0 Y080

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p><b>SUMMARY OF QUANTITIES</b></p> <p>SCALE _____ DRAWN BY KOJ</p> <p>DATE APRIL 18, 2008 CHECKED BY RGH</p>

PLOT DATE = 4/18/2008  
 FILE NAME = H:\4428\70804-1.dwg

H. M. & G. NO. 4420