

EARTHWORK SCHEDULE

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	1YRS, 2ZRS-1	CRAWFORD	378	19
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

LOCATION		EARTH EXCAVATION	EARTH EXCAVATION (WIDENING)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EMBANKMENT REQUIRED	EMBANKMENT REQUIRED FOR ENTRANCES (SEE NOTE)	EARTH EXCAVATION AVAILABLE (ADJUSTED FOR SHRINKAGE - 25%)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT	TOPSOIL BALANCE WASTE (+) OR SHORTAGE (-)
STATION		M2020010	M2020050	M2021200					MX032553	MX032879	
RT/LT	CU. M.	CU. M.	CU. M.	CU. M.	CU. M.	CU. M.	CU. M.	CU. M.	CU. M.	CU. M.	CU. M.
RURAL											
RT/LT	10207.7	316.9			4069.7	1120.3	7893.4	2703.5	3634.0	2970.0	664.0
RT.	173.3				44.0		130.0	86.0	23.8	101.6	-77.8
	10381.0	316.9	0.0		4113.7	1120.3	8023.4	2789.5	3657.8	3071.6	586.2
OBLONG											
RT/LT	1253.7				1416.6		940.3	-476.4	9.7	8.2	1.5
LT.	74.9				28.2		56.2	28.0			
LT.	45.2				8.9		33.9	25.0			
LT.	72.9				4.6		54.7	50.1			
LT.	63.0				2.9		47.3	44.4			
RT.	94.6				4.1		71.0	66.9			
LT.	16.5				5.1		12.4	7.3			
RT.	46.0				2.8		34.5	31.7			
LT.	45.7				4.3		34.3	30.0			
RT.	80.8				6.3		60.6	54.3			
LT.	18.6				7.1		14.0	6.9			
RT.	3.1				9.4		2.3	-7.1			
RT.	23.8				1.8		17.9	16.1			
LT.	37.3				1.3		28.0	26.7			
LT.	34.4				0.2		25.8	25.6			
RT.	26.2				2.6		19.7	17.1			
LT.	20.3				6.5		15.2	8.7			
RT.	47.2				5.6		35.4	29.8			
LT.	118.1				4.2		88.6	84.4			
LT.	15.8				28.0		11.9	-16.2			
RT.	16.6				38.5		12.5	-26.1			
RT.	33.0				3.2		24.8	21.6			
	2187.7	0.0	0.0		1592.2	0.0	1640.8	48.5	9.7	8.2	1.5
RURAL											
RT/LT	623.3	46.0			142.6	2066.7	502.0	-1707.3	300.6	180.0	120.6
RT/LT	19226.4	865.3			7737.8	6106.9	15068.8	1224.1	7666.1	6070.0	1596.1
RT.	127.8				44.0		95.9	51.9	19.0	16.7	2.3
LT.	68.8				72.5		51.6	-20.9	34.3	25.4	8.9
RT.	57.5				45.8		43.1	-2.7	37.5	27.4	10.1
LT.	62.8				18.7		47.1	28.4	28.8	19.1	9.7
RT.	56.0				21.6		42.0	20.4	33.9	24.9	9.0
LT.	65.6				12.0		49.2	37.2	14.3	18.9	-4.6
RT/LT	37501.7	1063.8	675.1		12074.9	13226.3	28924.1	3622.8	11454.2	9300.0	2154.2
LT.	40.8				7.0		30.6	23.6	24.8	25.3	-0.5
RT.	69.9				60.8		52.4	-8.4	25.3	34.8	-9.5
RT.	53.7				16.8		40.3	23.5	21.1	14.3	6.8
LT.	103.9				31.0		77.9	46.9	15.6	21.1	-5.5
RT.	123.8				14.0		92.9	78.9	8.0	21.5	-13.5
LT.	66.4				17.0		49.8	32.8	17.7	25.2	-7.5
RT.	155.2				3.0		116.4	113.4	30.8	27.9	2.9
LT.	103.1				23.0		77.3	54.3	19.3	13.9	5.4
RT.	63.6				3.0		47.7	44.7	25.0	20.9	4.1
	58570.2	1975.1	675.1		20345.5	21400.0	45409.0	3663.6	19776.2	15887.3	3888.9
URBAN											
RT/LT	2306.6	83.6			356.5	675.9	1792.7	760.3	720.9	570.0	150.9
RT.	50.3				10.0		37.7	27.7	11.3	9.4	1.9
RT.	56.7				3.0		42.5	39.5	9.5	10.1	-0.6
	2413.6	83.6	0.0		369.5	675.9	1872.9	827.5	741.7	589.5	152.2
TOTALS	73552.6	2375.6	675.1		26420.9	23196.2	56946.1	7329.1	24185.4	19556.6	4628.8
TOTALS ROUNDED FOR SUMMARY SHEET	73555	2380	680						24190	19560	

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION  <b>SCHEDULE OF QUANTITIES</b>  SCALE NO SCALE DRAWN BY KOJ DATE APRIL 18, 2008 CHECKED BY RGH
NAME	DATE	

PLOT DATE = 4/18/2008  
 FILE NAME = HY4428\72014\_sch\_e01\_schedu.res\_VB.dgn

H. M. & G. NO. 4420