

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	*	WABASH	36	3
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

(12Z,12,13)RS-3

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		1000 100% STATE	50% / 50% CITY / STATE
44200203	PAVEMENT PATCHING, TYPE II, 23 INCH	SQ YD	2058	2058	
44200205	PAVEMENT PATCHING, TYPE III, 23 INCH	SQ YD	733	733	
44200207	PAVEMENT PATCHING, TYPE IV, 23 INCH	SQ YD	374	374	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	294	294	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	18908	18339	569
40600300	AGGREGATE (PRIME COAT)	TON	378	367	11
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	565	565	
40600990	TEMPORARY RAMP	SQ YD	98	98	
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	15672	15313	359
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	223	223	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	16798	16798	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	175572	169880	5692
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SQ YD	13	13	
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SQ YD	31	31	
44200192	PAVEMENT PATCHING, TYPE II, 16 INCH	SQ YD	109	109	
44200196	PAVEMENT PATCHING, TYPE III, 16 INCH	SQ YD	31	31	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	4532	4532	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	320	320	
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4	

SUMMARY OF QUANTITIES (Cont'd)			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		1000 100% STATE	50% / 50% CITY / STATE
63200310	GUARDRAIL REMOVAL	FOOT	200	200	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	5	5	
67100100	MOBILIZATION	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	18254	18254	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	137789	137789	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	182	182	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	27	27	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2028	2028	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	20527	20527	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	182	182	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	27	27	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	117261	117261	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	766	766	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
Z0076600	TRAINEES	HOOR	500	500	

* SPECIALTY ITEMS

PLOT DATE = 1/16/2008
 FILE NAME = c:\pcc\94984\081703.dgn
 PLOT SCALE = 20.0000 / IN.
 USER NAME = ewarter

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. DATE
 HORIZ.

DRAWN BY
 CHECKED BY

Rex