

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	*	WABASH	36	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

• (12Z,12,13)RS-3

**PAVING SCHEDULE**

STATION	TO	STATION	PAVEMENT LENGTH	WIDTH	AREA	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT MIX ASPHALT SURFACE COURSE, MIX "C", NTO	HOT MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	HOT MIX ASPHALT SURFACE REMOVAL 1 1/2"	HOT MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	AGGREGATE SHOULDERS, TYPE B	TEMPORARY RAMP	PAVED SHOULDER REMOVAL
0+00.00	TO	5+70.50	570.5	24.0	1,521.3	240.8	4.8	127.8		1521.3	887.4			
5+70.50	TO	6+00.12	29.6	24.0	79.0	10.2	0.2	6.6		79.0	23.0			
6+00.12	TO	6+30.12	30.0	24.0	80.0	8.0	0.2	6.7	86.7				14.4	
6+30.12	TO	8+43.87	213.8	24.0	570.0	57.0	1.1							
8+43.87	TO	8+73.87	30.0	24.0	80.0	8.0	0.2	6.7	86.7				14.4	
8+73.87	TO	9+03.50	29.6	24.0	79.0	10.2	0.2	6.6		79.0	23.0			
9+03.50	TO	19+27.60	1,024.1	24.0	2,730.9	432.4	8.7	229.4		2730.9	1,593.0		29.3	
0+00.00	TO	9+61.29	961.3	24.0	2,563.4	448.6	8.9	215.3		2563.4	1,922.6			
9+61.29	TO	15+84.11	621.7	24.0	1,657.9	290.1	5.8	139.3		1657.9	1,243.4			
15+84.11	TO	16+14.11	30.0	38.4	128.0	12.8	0.3	10.8			80.0	1.2		
16+14.11	TO	16+34.00	19.9	31.0	68.5	6.9	0.1	5.8			53.0	1.6		
16+34.00	TO	42+64.10	2,630.1	27.0	7,890.3	789.0	15.8	662.8			8,767.0	178.4		
42+64.10	TO	88+64.07	4,558.5	27.0	13,675.6	1,367.6	27.4	1148.7			13,675.6	327.5		
88+64.07	TO	90+78.00	218.9	27.0	656.8	65.7	1.3	55.2			656.8	17.7		
90+78.00	TO	134+34.00	4,356.0	27.0	13,068.0	1,306.8	26.1	1097.7			13,068.0	310.2		
134+34.00	TO	134+64.00	30.0	27.0	90.0	9.0	0.2	7.6	80.0		90.0	2.4	13.3	
134+64.00	TO	136+36.00	172.0	27.0	516.0	51.6	1.0						13.3	
136+36.00	TO	136+66.00	30.0	27.0	90.0	9.0	0.2	7.6	80.0		90.0	2.4		
136+66.00	TO	192+98.80	5,632.8	27.0	16,898.4	1,689.8	33.8	1419.5			16,898.4	445.1		
192+98.80	TO	220+37.90	2,156.5	27.0	6,469.5	647.0	12.9	543.4			6,469.5	170.3		
220+37.90	TO	220+38.90	1.0	27.0	3.0	0.3		0.3			3.0	0.1		
220+38.90	TO	220+70.00	3.0	27.0	9.0	0.9		0.8			9.0	0.2		
220+70.00	TO	221+00.00	30.0	27.0	90.0	9.0	0.2	7.6			90.0	0.1		
221+00.00	TO	235+00.00	1,400.0	30.0	4,666.7	466.7	9.3	392.0		3733.3	933.3	145.2		1615.8
235+00.00	TO	235+30.00	30.0	27.0	90.0	9.0	0.2	7.6			90.0	0.3		
235+30.00	TO	250+22.90	1,492.9	27.0	4,478.7	447.9	9.0	376.2			4,478.7	115.2		
250+22.90	TO	414+19.30	16,396.0	27.0	49,188.0	4,918.8	98.4	4131.8			49,188.0	310.7		
414+19.30	TO	429+94.10	1,572.5	27.0	4,717.5	471.8	9.4	396.3			4,717.5	124.9		
429+94.10	TO	434+70.00	474.2	27.0	1,422.6	142.3	2.8	119.5			1,422.6	38.3		
434+70.00	TO	435+00.00	30.0	27.0	90.0	9.0	0.2	7.6			90.0	2.8		
435+00.00	TO	445+50.00	1,050.0	30.0	3,500.0	350.0	7.0	294.0		2800.0	700.0	108.1		427.6
445+50.00	TO	445+80.00	30.0	27.0	90.0	9.0	0.2	7.6			90.0	2.8		
445+80.00	TO	467+07.40	2,127.4	27.0	6,382.2	638.2	12.8	536.1			6,382.2	143.5		
467+07.40	TO	475+60.71	860.7	27.0	2,582.1	258.2	5.2	216.9			2,582.1	65.6		
475+60.71	TO	483+38.55	777.8	27.0	2,333.3	233.3	4.7	196.0			2,333.3	62.9		
483+38.55	TO	517+12.28	3,373.1	27.0	10,119.2	1,011.9	20.2	850.0			10,119.2	318.0		
517+12.28	TO	542+05.82	2,513.3	27.0	7,540.0	754.0	15.1	633.4			7,540.0	432.8		
542+05.82	TO	588+96.50	4,578.0	27.0	13,734.0	1,373.4	27.5	1153.7			13,734.0	370.2		
588+96.50	TO	600+16.83	1,116.8	27.0	3,350.5	335.0	6.7	281.4			3,350.5	84.5		
600+16.83	TO	600+46.83	30.0	27.0	90.0	9.0	0.2	7.6	80.0			2.4	13.4	
(HMA SHOULDER QTY)														
PROJECT TOTALS														
			61,232		183,389	18,908	378	15,672	413	15,165	173,394	4,786	98	2,043

PLOT DATE = 5/20/2007  
 FILE NAME = c:\msd\94984\94984.dwg  
 PLOT SCALE = 20.0000 / IN.  
 USER NAME = swb@tntm

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES**

SCALE: VERT. / HORIZ.  
 DATE:                      DRAWN BY:                      CHECKED BY: