


T.R.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
367	06-03113-00-BR	SHELBY	16	
STA. 5+00		TO STA. 15+00		
FED. ROAD DIST. NO.		ILLINOIS CONTRACT NO. 95533		
CLARKSBURG ROAD DISTRICT				



ELEANOR K. SHULMAN
SW 1/4, SEC 23, T. 10 N., R. 4 E., 3RD P.M.

STATION 10+00 - SPECIAL BRIDGE DESIGN
PRECAST PRESTRESSED CONCRETE DECK BEAM
BRIDGE, 3 SPANS: 31'-0", 64'-0", 31'-0"
24'-0" ROWY; SKEW = 10°
PROPOSED STRUCTURE NO. 087-3561

LYDIA LEWIS
NW 1/4, SEC 26, T. 10 N., R. 4 E., 3RD P.M.

CHANNEL EXCAVATION
THE CHANNEL SHALL BE EXCAVATED AS SHOWN IN THE PLANS WITH 2:1 SIDE SLOPES WITHIN THE LIMITS OF THE PROPOSED STRUCTURE, THEN TAPER TO THE EXISTING CHANNEL AT THE R.O.W. LINES. ONLY SUITABLE EXCAVATED MATERIAL SHALL BE USED IN THE EMBANKMENT.

EXISTING STRUCTURE NO. 087-3290
STATION 10+00 - TWO SPAN STEEL BEAM BRIDGE WITH CONCRETE DECK ON CLOSED TIMBER ABUTMENTS AND TIMBER PIERS.
97.0' FC-FC. ABUTS; 2L0' o-o. DECK
REMOVAL OF EXISTING STRUCTURES = 1 EACH

TEMPORARY DITCH CHECKS INDICATED
IN QUANTITIES TO ESTABLISH UNIT PRICE,
ENGINEER WILL DIRECT PLACEMENT IN FIELD.

DATE	BY	REVISION
02/27/79	LA. L. S.	PLAN
02/27/79	LA. L. S.	NOTE BOOK
02/27/79	LA. L. S.	ALIGNMENT CHECKED
02/27/79	LA. L. S.	RT. OF WAY CHECKED
02/27/79	LA. L. S.	NO. 10A NOTES
02/27/79	LA. L. S.	ROAD FILE NAME

DATE	BY	REVISION
02/27/79	LA. L. S.	PROFILE
02/27/79	LA. L. S.	GRADES CHECKED
02/27/79	LA. L. S.	BEAM NOTED
02/27/79	LA. L. S.	STRUCTURE RATINGS OK'D

