

ROUTE	SECTION	COUNTY	SHEET NO.	TOTAL SHEETS
FAS 79B	92-00063-01-RS	CLAY	2	11
FEDERAL ROAD DISTRICT 7		ILLINOIS	FEDERAL AID PROJ.	
CONTRACT NO. 95551				

GENERAL NOTES

- 1) THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS, SPECIAL PROVISIONS AND THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" ADOPTED JANUARY 1, 2007.
- 2) AT LEAST 48 HOURS BEFORE ANY EXCAVATING, CALL J.U.L.I.E. 1-800-892-0123 FOR UTILITY LOCATION INFORMATION.
- 3) FACTORS USED FOR QUANTITY CALCULATIONS ARE AS FOLLOWS:
AGGREGATE SURFACE COURSE 2.1 TONS / CU YD
- 4) THE COMMERCIAL ENTRANCE TO THE NCFPD FIRE HOUSE IS LOCATED FROM 197+40 LT TO 197+94 LT. THE CONTRACTOR SHALL SCHEDULE POURS SO THAT EMERGENCY ACCESS TO AND FROM THE FIRE HOUSE CAN BE MAINTAINED AT ALL TIMES.
- 5) TRANSVERSE CONSTRUCTION JOINTS SHALL REQUIRE #5 SMOOTH BARS 18" LONG AT 12" CENTERS. IT IS ANTICIPATED THAT TRANSVERSE CONSTRUCTION JOINTS WILL BE REQUIRED AT THE END OF EACH DAYS POUR AND AT BLOCKOUTS FOR ACCESS TO DRIVEWAYS AND SIDEROADS.

UTILITIES

(FOR INFORMATION ONLY)

AMEREN CIPS
1800 FORD AVENUE
EFFINGHAM, IL 62401
217-347-3141

TRUNKLINE GAS COMPANY
R.R. 1
JOHNSONVILLE, IL 62850
618-835-2251

FARM BUREAU OIL COMPANY
1200 REFINERY RD
MT. VERNON, IN. 47620
812-838-8513

WABASH TELEPHONE COOP.
210 S. CHURCH ST.
LOUISVILLE, IL 62858
618-665-3311

EJ WATER COOP.
P.O. BOX. 8
DIETERICH, IL. 62424
217-925-5566

CLAY ELECTRIC COOP
7784 OLD HWY 50
FLORA, IL. 62839
618-662-2171

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	QUANTITY
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	331.5
* 50105225	PIPE CULVERT REMOVAL (SPECIAL)	FOOT	16
54200433	PIPE CULVERTS, TYPE 1 RCCP 18"	FOOT	72
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1
54216930	REINFORCED CONCRETE PIPE TEE, 18" PIPE WITH 18" RISER	EACH	1
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	10
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	26
67100100	MOBILIZATION	L SUM	1
* 70100460	TRAFFIC CONTROL AND PROTECTION STANDARD 701306	L SUM	1
* 70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
Δ * 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	29,794
Δ 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	121
Δ 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	58
Δ 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	11
78300100	PAVEMENT MARKING REMOVAL	SQ FT	69
* X0324742	SURFACE REMOVAL 2", SPECIAL	SQ YD	96,782
* XX005348	AGGREGATE SHOULDERS (SPECIAL)	FOOT	73,024
Z0055300	RUMBLE STRIP	EACH	3
* XX007371	PORTLAND CEMENT CONCRETE PAVEMENT, FURNISHED	CU YD	14,912
* XX007372	PORTLAND CEMENT CONCRETE PAVEMENT, 5", PLACEMENT	SQ YD	54,852
* XX007373	PORTLAND CEMENT CONCRETE PAVEMENT, 6", PLACEMENT	SQ YD	40,759
* XX007374	PORTLAND CEMENT CONCRETE PAVEMENT, 7", PLACEMENT	SQ YD	1,277
* XX007375	PORTLAND CEMENT CONCRETE PAVEMENT, 8", PLACEMENT	SQ YD	757

* SEE SPECIAL PROVISIONS

Δ SPECIALTY ITEMS