

GENERAL NOTES

- 1. ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION, AS INDICATED BY THE SUB-NUMBER LISTED IN THE INDEX OF SHEETS, OR THE COPY OF THE STANDARD INCLUDED IN THESE PLANS. FOR CODED PAY ITEM DESCRIPTIONS, INCIDENTAL ITEMS, AND ALL MATERIAL SPECIFICATIONS, PLEASE REFER TO THE LATEST EDITION OF THE IDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION.
2. ANY FACILITIES WHICH ARE THE PROPERTY OF ANY PUBLIC UTILITY LOCATED WITHIN THE LIMITS OF CONSTRUCTION, SHALL BE RELOCATED OR ADJUSTED BY THEIR RESPECTIVE OWNERS...
3. THE TYPE, SIZE, AND LOCATION OF UTILITIES, AS DELINEATED IN THESE TOPOGRAPHIC LAND SURVEY DOCUMENTS AND/OR CIVIL ENGINEERING DESIGN DOCUMENTS, HAVE BEEN DETERMINED BY REVIEW OF AVAILABLE EXISTING "AS-BUILT" OR RECORD DRAWINGS, FIELD SURVEY OF J.U.L.I.E. MARKED UTILITIES, OR FIELD SURVEY OF ABOVE GROUND SURFACE UTILITY FEATURES...
4. THE ENGINEER AND OWNER FURTHER DO NOT WARRANT THAT ALL UTILITIES HAVE BEEN ILLUSTRATED ON THESE DOCUMENTS. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR CONTACTING J.U.L.I.E. FOR FIELD VERIFICATION OF ALL UTILITIES ON THE SITE PRIOR TO COMMENCEMENT OF CONSTRUCTION...
5. THE CONTRACTOR SHALL CONFINE HIS OPERATIONS TO THE AREA LOCATED WITHIN THE CONSTRUCTION LIMIT LINES, AS SHOWN ON THE PLANS. ANY AREA DISTURBED BEYOND THESE LIMITS SHALL BE RESTORED TO ITS ORIGINAL CONDITION AT THE CONTRACTOR'S EXPENSE.
6. ALL TEMPORARY AND PERMANENT EROSION CONTROL DEVICES SHALL BE LOCATED AS SHOWN ON THE ROADWAY DETAIL PLAN SHEETS.
7. IT IS THE CONTRACTOR'S RESPONSIBILITY TO INSURE THAT ALL EROSION AND DISPLACED SEDIMENT DOES NOT MIGRATE OFF SITE. IF UNEXPECTED EROSION OR SEDIMENTATION OCCURS (OR IF THE EROSION PLAN STRUCTURES BECOME DAMAGED), THE CONTRACTOR SHALL PROVIDE SUFFICIENT MEASURES TO REPAIR, REPLACE, OR INSTALL EROSION CONTROL STRUCTURES TO INSURE OFF-SITE DAMAGE DOES NOT OCCUR. ANY SEDIMENT OR EROSION DAMAGE WHICH OCCURS OFF-SITE SHALL BE REPAIRED BY THE CONTRACTOR AT HIS/HER EXPENSE.
8. THE CONTRACTOR SHALL STAGE ALL WORK IN SUCH A WAY AS TO MAINTAIN INGRESS AND EGRESS TO ALL ABUTTING PROPERTIES AT ALL TIMES DURING CONSTRUCTION AT NO ADDITIONAL PAYMENT.
9. ALL EARTH SURFACES DISTURBED BY CONSTRUCTION WITHIN CONSTRUCTION LIMITS, OR AS DIRECTED BY THE ENGINEER, SHALL BE SEEDED. THE FOLLOWING QUANTITIES HAVE BEEN INCLUDED IN THE PAY ITEM "SEEDING, CLASS 2" AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED:
0.1 ACRES SEEDING CL2
0.1 ACRES MULCH METHOD 2
10 LBS. NITROGEN FERTILIZER
10 LBS. PHOSPHORUS FERTILIZER NUTRIENT
10 LBS. POTASSIUM FERTILIZER NUTRIENT
SEEDING DATES:
FALL: AUG. 16 - DEC. 31
SPRING: JAN. 1 - MAY 31
(NO SEEDING SHALL BE DONE BETWEEN JUNE 1 AND AUG. 15)
10. ALL EXCAVATION ADJACENT TO THE EDGE OF PAVEMENT SHALL BE PROTECTED WITH EXTENDED LEG BARRICADES WITH APPROPRIATE LIGHTING.
11. NO OVERNIGHT LANE CLOSURES EXCEPT DURING RE-CONSTRUCTION OF THE INTERSECTION WITH ILLINOIS ROUTE 177 SHALL BE ALLOWED ON COUNTY HIGHWAY 12 (FAS 8633) OR ILLINOIS ROUTE 177. LANE CLOSURES SHALL BE RESTRICTED TO THE HOURS FROM 9:00 AM TO 2:00 PM LOCAL TIME, MONDAY THROUGH FRIDAY. DURING CONSTRUCTION AT THE INTERSECTION OF IL 177 AND CH 12, THE DETOUR ROUTE SHALL BE SIGNED ACCORDING TO SHEET 39 OF THESE PLANS.

SUMMARY OF QUANTITIES table with columns: CODE NO., ITEM, UNIT, TOTAL QUANTITIES. Includes items like EARTH EXCAVATION, TRENCH BACKFILL, SEEDING, CLASS 2, NITROGEN FERTILIZER NUTRIENT, etc.

SUMMARY OF QUANTITIES table with columns: CODE NO., ITEM, UNIT, TOTAL QUANTITIES. Includes items like PRECAST REINFORCED CONCRETE FLARED END SECTIONS, WATERPROOFING MEMBRANE SYSTEM, CONCRETE GUTTER, etc.

NOTE: * DENOTES SPECIALTY ITEMS

Legend table with columns: ITEM, EXISTING, PROPOSED. Includes symbols for SIGNS, TRAFFIC SIGNAL, TREES, BUSHES, etc.

Legend table with columns: ITEM, EXISTING, PROPOSED. Includes symbols for CULVERT FLARED END SECTION, DITCH CHECK, DIRECTION OF FLOW, etc.

LEGEND

Legend table with columns: EXISTING CENTER, EXISTING ELECTRIC, EXISTING FENCE, EXISTING GAS LINE, EXISTING RIGHT-OF-WAY, EXISTING SANITARY SEWER LINE, EXISTING STORM LINE, EXISTING TELEPHONE LINE, EXISTING TREE LINE, EXISTING WATER LINE, PROPOSED CENTER, PROPOSED ELECTRIC, PROPOSED FENCE, PROPOSED GAS LINE, PROPOSED SANITARY SEWER LINE, PROPOSED STORM LINE, PROPOSED OVERHEAD TELEPHONE LINE, PROPOSED UNDERGROUND TELEPHONE LINE, PROPOSED TREE LINE, PROPOSED WATER LINE.

CONTRACT NO. 97328

Kaskaskia Engineering Group L.L.C. 23 Public Square Suite 404 Belleville, Illinois 62220 Office: (618) 233-5977 Fax: (618) 233-5977 www.kaskaskiaeng.com A Disadvantaged Business Enterprise

PROFESSIONAL REGISTRATIONS LICENSE NO. 1840713 ILLINOIS PROFESSIONAL DESIGN FIRM PROFESSIONAL ENGINEERING CORP. 20-090688

PREPARED BY:

Table with columns: REV, DATE, DESCRIPTION. Includes revision entries for XXX/XX/XX.

GENERAL NOTES, LEGEND & SUMMARY OF QUANTITIES COUNTY HIGHWAY 12 (F.A.S. 833) SECTION 06-00080-00-RS RESURFACING & REHABILITATION WASHINGTON COUNTY, ILLINOIS

Table with columns: DESIGNED BY: CHA, DRAWN BY: CHA, CHECKED BY: TJM, DATE OF PRELIMINARY: 11/9/2007, DATE OF FINAL: 12/28/2007, SHEET NO. 2 OF 94 SHEETS, PROJECT NUMBER 06-0032