

F.A.U. ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
9170	03-00054-00-RP	ST. CLAIR	41	5
STA. 2+22.78		TO	STA. 37+18.35	
FEDERAL AID PROJECT			CONTRACT 97335	

ENTRANCE / SIDEROAD SCHEDULE

STATION	SURFACE	TYPE	"L"	"W"	DRIVEWAY P.V.M.T. REMOVAL SQ. YD.	INCIDENTAL HOT-MIX ASPHALT SURFACING TON	AGG. BASE COURSE, TY B-8" TON	P.C.C. DRIVEWAY PAVEMENT, 6" SQ. YD.	AGG. SURFACE COURSE, TY B-6" TON	HMA SURFACE CRSE., MIX "D", N70-2" TON	HMA BINDER CRSE., IL-19.0, N70-4" TON	COMMENTS
			FOOT	FOOT								
STA. 3+57 RT.	AGGREGATE	PE	11.5	15.0				15.9	1.0			
STA. 7+21 RT.	ASPHALT	SR*	7.0	32.5						5.4	10.8	STEVEN DEE DRIVE**
STA. 8+26 RT.	ASPHALT	PE	13.5	12.0	28.1	1.7	4.4	12.0				
STA. 9+61 RT.	ASPHALT	PE	20.0	19.4	45.0	5.0	13.1	17.0				
STA. 10+66 LT.	ASPHALT	CE*	4.0	28.0						3.0	6.1	S. PARK ENTRANCE
STA. 11+10 LT.	ASPHALT	CE*	5.0	28.0						3.3	6.7	N. PARK ENTRANCE
STA. 12+00 RT.	CONCRETE	CE	38.5	44.2***	112.3			87.1				LOADING DOCK
STA. 17+71 RT.	CONCRETE	PE	10.5	12.9	12.9			19.2				
STA. 18+92 RT.	ASPHALT	SR*	13.9	26.0						17.7	35.6	W. MADISON DRIVE
STA. 20+31 RT.	AGGREGATE	PE	20.1	17.2				17.2	8.7			
STA. 20+89 RT.	ASPHALT	PE	20.0	19.0	57.8	5.0	13.1	18.4				
STA. 21+53 RT.	ASPHALT	PE	10.1	20.3	17.6			19.3				
STA. 22+08 RT.	ASPHALT	PE	12.9	17.4	38.8	2.2	5.9	17.3				
STA. 22+98 RT.	CONCRETE	PE	13.5	16.0	36.9			29.7				
STA. 23+93 RT.	ASPHALT	SR*	5.1	24.0						15.6	31.2	W. NIXON DRIVE
STA. 25+44 RT.	ASPHALT	CE	13.9	30.7	44.3	4.5	11.9	26.2				
STA. 26+68 RT.	ASPHALT	CE	12.2	33.7	45.3	5.0	13.1	28.3				
STA. 27+17 RT.	OIL & CHIP	PE	13.8	12.4		1.8	4.9	14.1				
STA. 34+98 RT.	AGGREGATE	PE	12.7	15.5					7.3			
STA. 60+69 LT.	AGGREGATE	PE	15.5	13.0					9.5			
TOTAL					439.0	26.7	70.5	321.7	31.3	45.0	90.0	

(*) - MEASURED FROM EDGE OF OBERNEUFEMANN ROAD
 (**) - ENTRANCE WILL BE COMPLETED IN TWO HALVES UNDER STAGES 4 & 5
 (***) - MEASURED PARALLEL TO ROADWAY
 NOTE: OGLE ROAD AND PORTER ROAD INCLUDED IN PAVING SCHEDULE

THERMOPLASTIC PAVEMENT MARKINGS

LOCATION	SOLID DOUBLE YELLOW 4" LANE LINE	SOLID YELLOW 12" DIAGONAL LINE	SOLID WHITE 4" LANE LINE	SOLID WHITE TURN ARROW	SOLID WHITE 24"	SOLID WHITE 6" CROSSWALK LINE	WHITE SKIP DASH 4" LANE LINE	SOLID WHITE RAILROAD SYMBOL	SHORT TERM PAVEMENT MARKING
	FOOT	FOOT	FOOT	SQ. FT.	FOOT	FOOT	FOOT	SQ. FT.	FOOT
STA. 2+23 LT.					15				
STA. 2+23 TO 3+90 C	334								
STA. 3+23 LT.					13				70
STA. 3+23 TO 7+25 C								61.2	
STA. 3+48 LT.									
STA. 3+73 LT.					13				
STA. 3+90 TO 8+82 LT./C	1,873	186							
STA. 6+91 TO 6+97 C					30	22			
STA. 6+97 TO 7+50 RT.						92			
STA. 7+22 TO 7+40 RT.					18				
STA. 7+25 TO 11+30 C									100
STA. 8+82 TO 10+46 LT.	328								
STA. 8+82 TO 10+46 C			164						
STA. 9+29 LT.				15.6					
STA. 10+06 LT.				15.6					
STA. 10+98 TO 14+86 LT./RT.	1,510	152							90
STA. 11+30 TO 20+15 C									
STA. 14+86 TO 19+11 C	850								
STA. 19+14 C					36				
STA. 19+17 TO 24+10 C	986								
STA. 19+42 TO 23+44 RT.			416						
STA. 20+15 TO 30+30 C									40
STA. 23+80 TO 24+07 RT.						52			
STA. 24+13 C					36				
STA. 24+16 TO 28+38 C	844								
STA. 28+38 TO 31+09 LT./RT.	1,054	111							
STA. 30+30 TO 37+20 C									40
STA. 31+60 TO 32+98 LT.			135						
STA. 31+60 TO 32+98 RT.	276								
STA. 32+02 C				15.6					
STA. 32+51 C				15.6					
STA. 32+98 TO 33+33 RT.	137	6							
STA. 33+98 TO 36+68 LT./RT.	1,071	116							
STA. 36+68 TO 37+28 C	120								
STA. 50+34 C					34				
STA. 50+34 TO 50+90 LT.			56						
STA. 50+34 TO 52+31 RT./C	388								
STA. 50+42 C				15.6					
STA. 50+82 C				15.6					
STA. 50+90 TO 51+59 LT.						18			
STA. 3+19 TO 37+18									1055
TOTALS	9,772	559	771	93.6	195	166	18	61.2	1395

PAVEMENT / CURB & GUTTER REMOVAL SCHEDULE

LOCATION	PAVEMENT REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	GUTTER REMOVAL
	SQ. YD.	FOOT	FOOT
STA. 3+19.3 TO 3+25.3 RT.		6	
STA. 3+19.3 TO 3+28.6 LT.		10	
STA. 3+19.3 TO 7+25.0 C	1,072		
STA. 6+81.1 TO 6+98.9 RT.		21	
STA. 6+81.1 TO 7+63.4 RT.	48		
STA. 7+25.0 TO 11+30.0 C	1,058		
STA. 7+44.2 TO 7+63.4 RT.		23	
STA. 9+84.9 TO 12.10.3 LT.	369		
STA. 10+15.2 TO 10+28.0 LT.		14	
STA. 11+30.0 TO 20+15.0 C	2,346		
STA. 11+44.4 TO 11+50.7 LT.		7	
STA. 18+51.6 TO 19+30.8 RT.	104		
STA. 18+52.7 TO 18+77.6 RT.			41
STA. 19+06.6 TO 19+31.0 RT.			39
STA. 20+15.0 TO 30+30.0 C	2,841		
STA. 23+52.9 TO 23+79.4 RT.			42
STA. 23+52.9 TO 24+33.4 RT.	79		
STA. 24+07.4 TO 24+33.4 RT.			42
STA. 30+30.0 TO 37+18.4 C*	3,232		
TOTAL	11,149	81	164

(*) - QUANTITIES FOR OGLE & PORTER ROAD ARE INCLUDED IN THIS QUANTITY

SIDEWALK SCHEDULE

LOCATION	P.C.C. SIDEWALK, 4"	DETECTABLE WARNINGS
	SQ. FT.	SQ. FT.
STA. 2+30.6 TO 3+45.3 RT.	455	
STA. 3+68.6 TO 6+98.5 RT.	1,348	
STA. 6+88 TO 7+00 LT.	435	
STA. 6+93.7 LT.		12
STA. 6+94.3 RT.		8
STA. 7+45.0 TO 7+53.3 RT.	41	
STA. 7+48.9 RT.		8
STA. 19+07.6 TO 19+19.6 LT.	54	
STA. 19+10.9 TO 20+18.5 RT.	439	
STA. 19+13.6 LT.		12
STA. 19+14.1 RT.		8
STA. 20+43.7 TO 20+75.7 RT.	128	
STA. 21+02.7 TO 21+39.2 RT.	146	
STA. 21+67.4 TO 21+95.1 RT.	111	
STA. 22+20.4 TO 22+86.5 RT.	264	
STA. 23+10.5 TO 23+78.8 RT.	300	
STA. 23+77.0 RT.		8
STA. 24+07.0 TO 24+19.0 LT.	54	
STA. 24+08.5 TO 25+24.7 RT.	521	
STA. 24+10.8 RT.		8
STA. 24+13.0 LT.		12
STA. 24+13.6 RT.		8
STA. 25+63.3 TO 26+46.5 RT.	334	
STA. 26+88.2 TO 27+06.8 RT.	75	
STA. 27+27.2 TO 30+94.8 RT.	1,510	
TOTAL	6,215	84

E:\2131\213101\Oberneufemmann Road\Imp\05_06_SCH05.DWG, 3/16/2006, 8:57:20 AM, created by A.S.