

EARTHWORK SCHEDULE

LOCATION	A	B	C	D	E
	EARTH EXCAVATION (WIDENING)	REMOVAL OF UNSUITABLE MATERIAL	REMAINING MATERIAL	REQUIRED FILL	FURNISHED EXCAVATION
STATION	CU YD	CU YD	CU YD	CU YD	CU YD
SORENTO ROAD					
STA. 30+00.00 TO 34+83.00	53.2	53.2	0.0	61.7	61.7
STA. 34+83.00 TO 42+37.00	84.4	84.4	0.0	130.2	130.2
STA. 42+37.00 TO 57+24.00	224.0	224.0	0.0	463.6	463.6
STA. 57+24.00 TO 120+95.50	802.8	802.8	0.0	1,822.4	1,822.4
STA. 120+95.50 TO 167+41.00	455.8	455.8	0.0	692.7	692.7
STA. 167+41.00 TO 178+00.00	108.0	108.0	0.0	321.0	321.0
TOTALS	1,728.2	1,728.2	0.0	3,491.6	3,491.6
USE	1,729	1,729	0	3,492	3,492

- NOTES:**
 1. COLUMN "A" HAS BEEN ESTIMATED FROM CROSS SECTION AREAS & WILL CONTAIN MINIMAL AMOUNTS OF FRONT SLOPE & DITCH GRADING
 2. COLUMN "B" IS THE REMOVAL OF ANY UNSUITABLE EARTH EXCAVATION. FOR ESTIMATING PURPOSES, ALL EARTH EXCAVATION SHOULD BE CONSIDERED UNSUITABLE. ONLY FIELD MEASURED VOLUMES REMOVED FROM THE SITE WILL BE PAID FOR.
 3. COLUMN "C" IS THE REMAINING SUITABLE MATERIAL THAT MAY BE USED FOR FILL. COLUMN "C" IS NOT A PAY ITEM.
 4. COLUMN "D" REPRESENTS THE TOTAL REQUIRED FILL FOR THE PROJECT. COLUMN "D" IS NOT A PAY ITEM.
 5. COLUMN "E" REPRESENTS THE ESTIMATED FURNISHED EXCAVATION (COLUMN "C" - COLUMN "D")

PATCHING SCHEDULE

LOCATION			A	B	C
			CLASS D PATCHES, TYPE II, 6 INCH	CLASS D PATCHES, TYPE III, 6 INCH	CLASS D PATCHES, TYPE IV, 6 INCH
SORENTO ROAD			SQ YD	SQ YD	SQ YD
STATION	LENGTH	WIDTH			
	FT	FT			
RIGHT 40+00	140	6			93.3
RIGHT 47+75	70	8			62.2
LEFT 80+25	15	8	13.3		
CENTER 79+50	35	15			58.3
LEFT 81+00	105	8			93.3
ALL 84+00	70	22			171.1
RIGHT 89+10	10	10	11.1		
LEFT 89+20	10	10	11.1		
RIGHT 92+00	10	10	11.1		
RIGHT 92+75	35	10			38.9
LEFT 93+00	55	10			61.1
RIGHT 95+75	10	10	11.1		
ALL 102+00	140	22			342.2
RIGHT 117+00	30	6		20	
LEFT 117+00	210	6			140
ALL 124+50	25	22			61.1
CENTER 155+00	420	8			373.3
CENTER 160+00	70	6			46.7
ALL 168+10	25	22			61.1
TOTALS			57.7	20.0	1,602.6
USE			58	20	1,603

APPROXIMATE AREAS AND LOCATIONS SHOWN ABOVE. ACTUAL DIMENSIONS TO BE DETERMINED IN FIELD. QUANTITIES MAY BE SUBSTANTIALLY REDUCED AFTER FIELD INSPECTION BY ENGINEER.

FILE NAME = H:\5592\Sch.Quant.55'12.dgn

USER NAME = .USERDESCR.

DESIGNED - DLD

REVISED -

DRAWN - KOJ

REVISED -

PLOT SCALE = 5,0000' / IN.

CHECKED -

REVISED -

PLOT DATE = 3/21/2008

DATE - 1-17-08

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: NONE SHEET NO. OF SHEETS STA. TO STA.

F.A.S RTE.

777

SECTION

05-00080-00-RS

COUNTY

BOND

TOTAL SHEETS

90

SHEET NO.

6

CONTRACT NO. 97341

FED. ROAD DIST. NO. 8 ILLINOIS FED. AID PROJECT