

PAVING SCHEDULE

LOCATION	A	B	C	D	E	F	G	H	I	J
	AGGREGATE BASE COURSE, TYPE A, 12"	HOT-MIX ASPHALT BASE COURSE WIDENING, 6"	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMPS	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT BINDER COURSE, 1L-19.0, N50 (VAR)	HOT-MIX ASPHALT BINDER COURSE, 1L-19.0, N50 (3 1/2")	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	INCIDENTAL HOT-MIX ASPHALT SURFACING
STATION	SO YD	SO YD	SO YD	SO YD	GALLON	TON	TON	TON	TON	TON
SORENTO ROAD										
RT 29+99.90 TO 34+83.00	53.7									
LT 29+99.90 TO 34+68.45	52.1									
RT 34+83.00 TO 42+11.02	85.0									
LT 34+99.24 TO 42+37.00	180.6									
LT 42+37.00 TO 57+24.00	215.3									
RT 42+59.43 TO 57+24.00	186.2									
LT 57+24.00 TO 120+95.50	942.0									
RT 57+24.00 TO 120+95.50	831.8									
LT 125+00.0 TO 158+12.00		697.9								
RT 125+00.0 TO 167+41.77		644.4								
LT 158+12.00 TO 167+13.89		177.9								
RT 167+41.77 TO 178+00.00		154.1								
LT 167+56.11 TO 173+20.54		43.5								
LT 173+20.54 TO 178+00.00		44.5								
30+00.0 TO 34+83.00					330.6	7.1		235.6	109.70	
34+83.0 TO 42+37.00					516.1	11.1		367.8	171.30	
42+37.0 TO 57+24.00					1017.7	21.8		725.3	337.80	
57+24.0 TO 120+95.50					4360.9	93.5		3,108.0	1447.30	
125+00. TO 167+41.77					1451.6	31.1			963.50	
167+41. TO 178+00.00					362.1	7.8			240.40	
30+00.0 TO 34+83.00							52.7			
34+83.0 TO 42+37.00							113.5			
42+37.0 TO 57+24.00							772.0			
57+24.0 TO 120+95.50							2477.1			
120+95. TO 167+41.00							1756.8			
167+41. TO 178+00.00							198.9			
34+83.00 CRANE RD			14.7		6.4	0.1				10.68
42+37.00 LAKE RD			65.7		21.9	0.5				11.86
57+24.00 PLEASANT AVE			263.4		36.9	0.8				43.20
167+41.00 DOVE RD			12.4		16.9	0.4				22.49
30+00.00 MAINLINE START			122.2							
120+95.00 BRIDGE START			122.2							
125+00.00 BRIDGE END			122.2							
178+00.00 MAINLINE END			122.2							
MLLING 30+00.0 TO 30+05.00				12.22						
1ST LIFT 30+40.0 TO 30+50.00				24.44						
2ND LIFT 30+40.0 TO 30+50.00				24.44						
2ND LIFT 120+45. TO 120+55.00				24.44						
1ST LIFT 120+45. TO 120+55.00				24.44						
MLLING 120+90. TO 120+95.00				12.22						
MLLING 125+00. TO 125+05.00				12.22						
1ST LIFT 125+40. TO 125+50.00				24.44						
2ND LIFT 125+40. TO 125+50.00				24.44						
2ND LIFT 177+50. TO 177+60.00				24.44						
1ST LIFT 177+50. TO 177+60.00				24.44						
MLLING 177+95. TO 178+00.00				12.22						
TOTALS	2,546.7	1,762.3	845.0	244.4	8,121.1	174.2	5,371.0	4,436.7	3,270.0	88.2
USE	2,547	1,763	845	245	8,122	175	9,808	3,270	88	

SHOULDER SCHEDULE

LOCATION	AGGREGATE SHOULDERS, TYPE A 4"
STATION	SO YD
SORENTO ROAD	
RT 29+99.89 TO 34+51.14	149.81
LT 29+99.90 TO 34+68.53	154.68
RT 34+72.86 TO 41+05.41	208.91
LT 34+99.94 TO 47+97.81	429.67
RT 41+41.70 TO 42+12.42	20.39
RT 42+58.33 TO 48+70.03	201.33
LT 48+42.95 TO 56+33.47	432.61
RT 48+93.97 TO 61+44.64	572.85
LT 57+39.27 TO 73+37.04	526.27
RT 61+65.36 TO 74+71.75	543.11
LT 73+54.96 TO 86+22.67	420.11
RT 74+90.25 TO 75+25.25	10.26
RT 75+44.75 TO 88+02.03	417.64
LT 86+45.33 TO 87+62.78	37.70
LT 87+87.22 TO 92+72.64	160.79
RT 88+21.97 TO 92+78.54	149.93
LT 92+95.36 TO 94+90.61	63.21
RT 93+09.46 TO 101+78.54	283.57
LT 95+21.46 TO 104+19.03	300.49
RT 102+07.46 TO 107+45.54	177.09
LT 104+51.51 TO 109+73.64	172.17
RT 107+78.46 TO 116+95.09	189.60
LT 109+92.36 TO 120+95.50	604.93
RT 117+89.51 TO 120+95.50	101.04
RT 125+00.00 TO 127+66.78	88.85
LT 125+00.00 TO 146+79.54	723.14
RT 128+74.69 TO 132+57.11	126.34
RT 132+80.18 TO 165+28.06	1225.60
LT 147+10.46 TO 158+03.14	468.50
LT 158+20.86 TO 162+68.10	147.30
LT 162+85.90 TO 163+85.06	31.49
LT 164+24.94 TO 167+09.16	92.07
RT 165+49.94 TO 178+00.00	611.66
LT 167+67.04 TO 178+00.00	536.23
TOTALS	10,379.3
USE	10,380

HENRY, MEISENHEIMER & GENDE, INC., 1075 LAKE ROAD, PO BOX 70, CARLYLE, IL 62231 PHONE (618) 594-3711 WWW.HMENGINEERS.COM