FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
9392	05-00024--00-PV	MADISON	81	5
STA.	TO STA.			

CONTRACT NO. 97347

STORM SEWER SCHEDULE

FROM STATION	OFFSET (FEET)	TO STATION	OFFSET (FEET)	SIZE AND LENGTH OF PIPE (FEET)													TRENCH BACKFILL (CU YD)
				12" CL A, TY 1	12" CL A, TY 2	15" CL A, TY 1	18" CL A, TY 1	18" CL A, TY 2	36" CL A, TY 1	18" CL B, TY 1	24" CL B, TY 1	12" PVC SDR 26	15" PVC SDR 26	18" PVC SDR 26	24" PVC SDR 26	36" PVC SDR 26	
N. HICKORY ST./N. STAUNTON ROAD																	
10+35.71	37.28' LT	10+26.14	29.46' LT	10													2.12
10+26.14	29.46' LT	10+36.03	18.66' LT	11.5													2.60
10+36.03	18.66' LT	11+73.76	22.00' LT		134.5												38.98
11+25.00	14.56' RT	12+37.88	14.56' RT	110													18.85
11+73.76	22.00' LT	12+90.35	14.65' LT		114												22.21
12+37.88	14.56' RT	12+93.01	14.00' RT		52												10.90
12+82.63	41.30' LT	12+90.35	14.65' LT	25													2.59
13+04.08	22.91' LT	12+90.35	14.65' LT		13												0.63
12+90.31	14.65' LT	12+93.01	14.00' RT									25					8.52
12+93.01	14.00' RT	13+09.78	20.63' RT		15												4.69
13+43.16	26.41' LT	13+04.08	22.91' LT									36					6.45
13+48.43	101.99' LT	13+43.16	26.41' LT	70													–
15+07.12	17.58' LT	15+07.12	14.00' RT	28.5													4.82
15+07.12	14.00' RT	15+58.13	17.62' RT	48.5													10.09
15+58.13	17.62' RT	15+68.63	31.77' RT									14.5					2.51
15+68.63	31.77' RT	15+94.41	34.68' RT		22.5												4.33
15+98.48	17.58' LT	15+94.41	34.68' RT											49			16.35
17+29.42	14.56' LT	16+83.45	19.41' LT			44											4.33
16+83.45	19.41' LT	15+98.48	17.58' LT			83											25.38
17+29.42	14.56' RT	17+29.42	14.56' LT	26													5.93
17+39.42	14.56' RT	17+29.42	14.56' RT	7.5													1.64
17+39.42	14.56' LT	17+29.42	14.56' RT			7											1.63
18+41.08	17.58' LT	17+39.42	14.58' LT	98.5													20.59
18+41.08	14.56' RT	18+41.08	17.58' LT	30													5.45
19+04.05	17.58' LT	18+41.08	17.58' LT		60												11.31
19+89.42	17.58' LT	19+04.05	17.58' LT		82.5												15.56
19+89.42	14.56' RT	19+89.42	17.58' LT	30													5.77
21+13.59	70.62' LT	21+41.75	70.23' LT			25											7.06
21+41.64	108.85' LT	21+41.75	70.23' LT			36											–
21+41.75	70.23' LT	21+43.80	27.39' LT				40										–
21+43.80	27.39' LT	21+60.97	17.92' LT					16.5									4.54
21+60.97	17.92' LT	21+54.91	17.28' RT					33.5									10.01
21+54.91	17.28' RT	21+42.77	31.55' RT											15			5.27
22+62.90	17.58' LT	21+60.97	17.92' LT		98.5												26.07
23+52.41	41.21' LT	23+51.64	17.58' LT		21												2.08
23+64.09	17.58' LT	23+51.64	17.58' LT		10												2.33
23+51.64	17.58' LT	22+62.90	17.58' LT		86												22.49
23+64.09	14.00' RT	23+64.09	17.58' LT	28.5													6.27
21+70.92	35.23' RT	23+64.09	14.00' RT									20					3.94
24+88.47	17.58' LT	23+64.09	17.58' LT		121.5												24.25
25+06.19	16.97' RT	24+88.47	17.58' LT	37													7.48
27+63.82	14.56' RT	27+63.82	17.58' LT	30													6.53
27+63.82	17.58' LT	29+33.78	17.58' LT		167												36.05
29+33.78	17.58' LT	29+43.78	17.58' LT		7												1.55
29+33.78	14.56' RT	29+43.78	14.56' RT									7.5					1.77
29+43.78	14.56' RT	29+43.78	14.56' RT	29													6.97
29+43.78	17.58' LT	31+26.20	17.58' LT		179.5												37.14
31+26.20	17.58' LT	31+26.19	14.00' RT		28.5												5.97
31+26.19	14.00' RT	33+16.55	13.28' RT										186				44.49
32+47.16	27.28' LT	32+47.03	17.58' LT	7													1.29
32+47.03	17.58' LT	33+16.55	18.58' LT		66												15.39
33+16.55	18.58' LT	33+16.55	13.28' RT						26								10.79
33+16.55	27.90' LT	33+16.55	18.58' LT	7													0.93
33+26.55	14.56' RT	33+16.55	13.28' RT										6				1.42
33+16.55	13.28' RT	33+21.33	41.20' RT												24		8.45
33+21.33	41.20' RT	33+20.71	138.54' RT												93		–
33+31.55	17.58' LT	33+16.55	18.58' LT					11									4.09
33+82.08	28.49' LT	33+31.55	17.58' LT					48									15.43
33+81.01	53.44' LT	33+82.08	28.49' LT					18									1.41
34+01.62	14.00' RT	33+26.55	14.56' RT										72.5				16.84
34+11.00	46.64' LT	34+10.14	29.68' LT			10											0.83
34+10.14	29.68' LT	33+82.08	28.49' LT					24									7.08
34+70.21	17.58' LT	34+10.14	29.68' LT		58												16.29
35+78.61	17.58' LT	34+70.21	17.58' LT		105.5												25.43
36+09.74	21.44' LT	35+78.61	17.58' LT	29													–
35+92.06	16.96' RT	35+78.61	17.58' LT	34													7.52
36+09.61	17.07' RT	35+92.06	16.96' RT									15					2.80
CLAY STREET																	
10+19.58	20.48' RT	12+02.85	22.63' RT									180.5					36.40
12+02.85	22.63' RT	13+88.74	22.50' RT									185					10.91
BRYN STREET																	
10+33.42	12.00' LT	12+82.91	12.28' LT							251							13.45
THROP STREET																	
10+31.43	14.83' LT	11+77.25	17.74' LT							142.5							9.98
11+77.25	17.74' LT	12+36.97	17.19' LT							56.5							5.68
12+36.97	17.19' LT	13+23.51	16.39' LT							83							4.81
13+23.51	16.39' LT	13+43.11	31.41' RT												47.5		14.21
13+43.11	31.41' RT	13+41.09	111.53' RT								78						–
TOTAL				697	1,442	205	40	151	26	533	78	484	265	64	48	117	755.32

REVISIONS	
NAME	DATE

SCHEDULES

NORTH STAUNTON ROAD IMPROVEMENTS
CITY OF TROY
MADISON COUNTY, ILLINOIS

P:\030131\dwg\030131SCHED.dwg 2/1/2008 2:17:53 PM CST