

APP. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9392	05-00024-00-PV	MADISON	81	7
STA.		TO STA.		

CONTRACT NO. 97347

SEEDING SCHEDULE								
STATION	TO	STATION	SEEDING CLASS 2(ACRE)	NITROGEN FERTILIZER NUTRIENT (POUND)	PHOSPHORUS FERTILIZER NUTRIENT (POUND)	POTASSIUM FERTILIZER NUTRIENT (POUND)	MULCH METHOD 2 (ACRE)	TEMP. EROSION CONTROL SEEDING (ACRE)
N. HICKORY ST./N. STAUNTON RD.								
10+19.84	TO	36+65.40	1	90	90	90	1	1
TOTAL			1	90	90	90	1	1

POLYUREA PAVEMENT MARKINGS					
STATION	LOCATION	4" SOLID DOUBLE YELLOW LINE	4" SOLID WHITE LINE	6" SOLID WHITE LINE	12" SOLID WHITE LINE
		FEET	FEET	FEET	FEET
N. HICKORY ST./N. STAUNTON RD.					
10+31.45	CROSS WALK			82.38	
10+38.46	STOP BAR				16.48
10+38.46	TO 36+03.61	4859.82			
10+62.46	TO 12+70.37		218		
10+37	TO 12+88 LT				
12+93.75	RT STOP BAR				12.94
13+01.26	CROSS WALK			63.95	
13+20.14	LT STOP BAR				16.89
13+25.06	LT CROSS WALK			79.07	
13+32.00	RT CROSS WALK			65.79	
13+37.73	RT STOP BAR				13.24
13+61.47	CROSS WALK			55.60	
13+68.30	LT STOP BAR				13.00
15+81.81	RT CROSS WALK			63.27	
15+87.72	RT STOP BAR				11.00
20+97.54	RT STOP BAR				14.15
21+23.17	LT STOP BAR				13.28
21+27.88	RT CROSS WALK			69.93	
21+34.52	RT STOP BAR				13.22
21+58.23	LT STOP BAR				13.82
24+78.54	RT CROSS WALK			69.95	
24+85.73	RT STOP BAR				13.16
33+90.54	LT STOP BAR				13.28
35+65.61	RT CROSS WALK			69.94	
35+72.22	RT STOP BAR				13.29
TOTAL		4859.82	218	619.58	177.75

PIPE CULVERT REMOVAL				
STATION	TO	STATION	PIPE CULVERT REMOVAL (FEET)	TRENCH BACKFILL (CU. YD.)
N. HICKORY STREET/N. STAUNTON RD.				
12+85.20	TO	13+02.69	19.55	--
13+05.16	TO	13+14.01	173.44	1.91
13+48.02	TO	13+54.91	128.61	--
13+54.91	TO	13+62.82	185.03	--
16+01.61	TO	15+61.46	305.27	--
16+01.88	TO	16+19.16	17.38	--
15+97.31	TO	16+13.46	16.26	--
16+58.86	TO	16+74.30	15.35	--
16+59.87	TO	16+81.36	21.58	--
17+49.72	TO	17+73.76	24.02	--
18+10.10	TO	18+26.17	16.1	--
18+14.42	TO	18+30.72	16.32	--
18+73.90	TO	18+90.00	16.09	--
19+15.57	TO	19+32.08	16.51	--
20+16.47	TO	20+28.47	12.01	--
21+07.42	TO	21+41.11 LT	33.77	--
21+13.80	TO	21+14.44	7.74	--
21+41.64	TO	21+41.06	89.37	--
21+44.21	TO	21+49.13	4.98	--
23+21.17	TO	23+25.82	4.65	--
23+33.79	TO	23+49.80	16.02	--
27+31.18	TO	27+51.00	19.82	--
27+82.57	TO	28+02.55	19.98	0.39
27+84.55	TO	28+00.45	15.9	--
28+25.30	TO	28+64.45	39.17	--
28+45.93	TO	28+76.36	30.45	0.56
29+23.77	TO	31+16.07	192.19	--
29+54.75	TO	29+83.08	28.33	--
30+31.78	TO	30+51.23	19.47	--
31+31.86	TO	31+51.23	19.32	--
31+33.68	TO	31+57.91	24.23	0.44
32+03.65	TO	32+32.66	29.02	--
32+69.94	TO	33+56.92	87.07	13.89
32+74.69	TO	32+95.35	20.67	--
33+17.50	TO	33+21.33	58.58	--
33+21.33	TO	33+19.71	92.47	--
33+60.90	TO	33+90.63	29.75	3.87
33+77.23	TO	34+11.53	34.3	1.51
35+42.76	TO	35+78.81	36.11	--
35+46.33	TO	35+66.73	20.42	--
THROP STREET				
10+47.15	TO	10+65.00	43.80	1.21
10+47.15	TO	10+65.00	17.86	--
11+92.47	TO	12+33.16	40.69	--
12+46.25	TO	12+69.74	23.5	--
TOTAL			2083.15	23.78

INLET REMOVAL	
STATION	REMOVING INLETS
EACH	
N. STAUNTON ROAD	
13+04.47	LT 1
13+54.91	RT 1
16+01.46	LT 1
33+19.71	RT 1
33+21.33	RT 1
33+58.36	RT 1
35+79.74	RT 1
CLAY ST.	
13+88.74	RT 1
THROP ST.	
9+29.38	RT 1
TOTAL	
9	

TREE REMOVAL		
STATION	6-15 UNITS DIAMETER	OVER 15 UNITS DIAMETER
	UNIT	UNIT
N. STAUNTON ROAD		
10+80.26	LT 6	
11+43.87	LT 8	
23+70.75	RT	30
30+49.61	LT	30
31+51.43	RT 12	
31+59.55	RT 12	
31+63.32	RT 12	
32+23.00	RT	36
34+06.02	RT 6	
TOTAL		96

THERMOPLASTIC PAVEMENT MARKINGS			
STATION	LOCATION	4" SOLID DOUBLE YELLOW LINE	4" SOLID WHITE LINE
		FEET	FEET
N. STAUNTON ROAD			
14+43.85	LT PARKING SPACES		185
BYRN STREET			
10+34.77	TO 11+070.39	146	
TOTAL		146	185

REVISIONS	
NAME	DATE

SCHEDULES

NORTH STAUNTON ROAD IMPROVEMENTS
CITY OF TROY
MADISON COUNTY, ILLINOIS

P:\030131\dwg\030131SCH.DWG 2/1/2008 2:17:53 PM CST