

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
103	102RS-4	PERRY	13	5
STA.		TO STA.		
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

SUMMARY OF QUANTITIES

STP-RURAL-STATE
80% FED / 20% STATE
PERRY COUNTY
CONSTRUCTION TYPE
CODE I000

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
X0322729	MATERIAL TRANSFER DEVICE	TON	4,261.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	9,255.0
40600300	AGGREGATE (PRIME COAT)	TON	153.5
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	2,127.0
40600895	CONSTRUCTING TEST STRIP	EACH	1.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	675.0
40600990	TEMPORARY RAMP	SQ YD	18.0
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIXTURE C, N90	TON	4,261.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACE	TON	67.0
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	50,504.0
44201798	CLASS D PATCHES, TYPE I, 13 INCH	SQ YD	25.0
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	690.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	442.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2.0
67100100	MOBILIZATION	L SUM	1.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2,103.0
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	39,880.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	13,854.0
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	39,880.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	220.0

* SPECIALTY ITEMS

SUMMARY OF QUANTITIES