

F.A.C. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
103	102RS-4	PERRY	13	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SIDEROAD RESURFACING SCHEDULE

STATION LT. or RT.	SIDE ROAD NAME	SURFACE TYPE	WIDTH AT EDGE OF PAVEMENT (FT)	DISTANCE TO END OF SURFACING (FT)	WIDTH AT END OF SURFACING (FT)	SURFACE AREA (SQ YD)	HMA SURFACE REMOVAL-BUTT JOINT (SQ YD)	BITUMINOUS MATERIAL PRIME COAT (GAL)	AGGREGATE PRIME COAT (TON)	INCIDENTAL HMA SURFACE (TON)
Rt. 338+26.5	Coulterville Rd.	Bit.	224	15	113	281	281	25.3	0.42	24
Rt. 396+36	Columbine Rd.	Bit.	55	15	26	68	68	6.1	0.10	6
Rt. 453+37	Snapdragon Rd.	Oil & Chip	60	15	27	73		6.5	0.11	12
Rt. 482+52	Rejoice	Bit.	70	15	30	83	83	7.5	0.13	7
Lt. 396+36	Columbine Rd.	Bit.	51	15	21	60	60	5.4	0.09	5
Lt. 425+39	Buttercup Rd.	Agg.	52	15	19	59		5.3	0.09	10
TOTALS:							492	56	0.94	64

ENTRANCES RESURFACING SCHEDULE

NUMBER	ENTRANCE TYPE	SURFACE TYPE	WIDTH AT EDGE OF PAVEMENT (FT)	DISTANCE TO END OF SURFACING (FT)	WIDTH AT END OF SURFACING (FT)	SURFACE AREA (SQ YD)	HMA SURFACE REMOVAL-BUTT JOINT (SQ YD)	BITUMINOUS MATERIAL PRIME COAT (GAL)	AGGREGATE PRIME COAT (TON)	INCIDENTAL HMA SURFACE (TON)	AGGREGATE WEDGE (TON)
29	PRIVATE ENTRANCE	AGGREGATE	20	4	12	258		82.5	0.4	2.41	0.15
1	PRIVATE ENTRANCE	BITUMINOUS	20	4	12	9	9	0.8	0.01	0.06	
1	COMMERCIAL ENT	AGGREGATE	30	4	25	13		4.3	0.02	0.08	0.32
TOTALS:							9	88	0.4	3	0.47

* AGGREGATE WEDGE QUANTITY TO BE INCLUDED IN COST OF AGGREGATE SHOULDER, TY. B.

PLOT DATE = 2/13/2008
 PLOT SCALE = 1/8" = 100'
 PLOT NAME = 102RS-4 / 9
 USER NAME = mboarder