

DATE	REVISION	BY

SUMMARY OF QUANTITIES - BASE BID

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AR108088	1/C #8 XLP-USE	L.F.	2100	
AR108108	1/C #8 5KV UG CABLE	L.F.	620	
AR108158	1/C #8 5KV UG CABLE IN UD	L.F.	640	
AR108258	2/C #8 5KV UG CABLE IN UD	L.F.	2,110	
AR108652	3/C #2 600V UG CABLE IN UD	L.F.	300	
AR108658	3/C #8 600V UG CABLE IN UD	L.F.	4,220	
AR108812	12 PAIR CONTROL CABLE	L.F.	940	
AR109200	INSTALL ELECTRICAL EQUIPMENT	L.S.	1	
AR110014	4" DIRECTIONAL BORE	L.F.	1,055	
AR110610	ELECTRICAL HANDHOLE	EACH	4	
AR125415	MITL - BASE MOUNTED	EACH	1	
AR125445	TAXI GUIDANCE SIGN, 5 CHARACTER	EACH	1	
AR125565	SPLICE CAN	EACH	8	
AR125901	REMOVE STAKE MOUNTED LIGHT	EACH	4	
AR125961	RELOCATE STAKE MOUNTED LIGHT	EACH	2	
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR150530	TRAFFIC MAINTENANCE	L.S.	1	
AR150540	HAUL ROUTE	L.S.	1	
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	1,184	
AR156510	SILT FENCE	L.F.	600	
AR156511	DITCH CHECK	EACH	2	
AR156513	SEPARATION FABRIC	S.Y.	8,942	
AR156531	EROSION CONTROL BLANKET	S.Y.	227	
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	2,057	
AR401665	BITUMINOUS PAVEMENT SAWING	L.F.	591	
AR501506	6" PCC PAVEMENT	S.Y.	8,915	
AR501530	PCC TEST BATCH	EACH	1	
AR510510	TIE DOWN	EACH	9	
AR510515	GROUND ROD	EACH	2	
AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	1,436	
AR620525	PAVEMENT MARKING-BLACK BORDER	S.F.	1,434	
AR701518	18" RCP, CLASS IV	L.F.	159	
AR751410	INLET	EACH	1	
AR751940	ADJUST INLET	EACH	2	
AR752418	PRECAST REINFORCED CONC, FES 18"	EACH	1	
AR901510	SEEDING	ACRE	0.50	
AR908510	MULCHING	ACRE	0.50	

SUMMARY OF QUANTITIES - BID ALTERNATE NO. 1

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AS106503	APRON LIGHT POLE W/TRIPLE FIXTURE	EACH	1	
AS106611	TYPE A ASSEMBLY - 1 FIXTURE	EACH	1	
AS108658	3/C #8 600V UG CABLE IN UD	L.F.	200	
AS109620	LIGHTING CONTROL SYSTEM	L.S.	1	

INDEX TO SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES AND INDEX TO SHEETS
3	PROPOSED SAFETY PLAN
4	EXISTING SITE PLAN
5	PROPOSED CONSTRUCTION PLAN
6	EXISTING AND PROPOSED TYPICAL SECTIONS
7	PROPOSED STORM WATER POLLUTION PREVENTION PLAN
8	PROPOSED DRAINAGE PLAN
9	PROPOSED DRAINAGE DETAILS
10	PROPOSED DRAINAGE DETAILS
11	PROPOSED STAKING PLAN
12	PROPOSED JOINTING PLAN
13	PROPOSED JOINTING DETAILS
14	PROPOSED ELECTRICAL PLAN
15	PROPOSED ELECTRICAL PLAN-CONTINUED
16	PROPOSED ELECTRICAL DETAILS SHEET 1
17	PROPOSED ELECTRICAL DETAILS SHEET 2
18	PROPOSED ELECTRICAL DETAILS SHEET 3
19	ELECTRICAL NOTES SHEET 1
20	ELECTRICAL NOTES SHEET 2
21	ELECTRICAL LEGEND AND ABBREVIATIONS
22	VAULT & AIRFIELD ELECTRICAL ONE LINE DIAGRAM
23	ELECTRICAL ONE LINE DIAGRAM FOR APRON LIGHTING & AWOS
24	PROPOSED APRON LIGHTING CONTROLLER
25	APRON LIGHTING DETAILS
26	PROPOSED MARKING PLAN
27	PROPOSED CROSS-SECTIONS FOR RAMP EXPANSION STA. 47+50 TO STA. 48+50
28	PROPOSED CROSS-SECTIONS FOR RAMP EXPANSION STA. 48+75 TO STA. 49+75
29	PROPOSED CROSS-SECTIONS FOR RAMP EXPANSION STA. 49+92 TO STA. 50+75
30	PROPOSED CROSS-SECTIONS FOR RAMP EXPANSION STA. 51+00 TO STA. 52+00
31	PROPOSED CROSS-SECTIONS FOR RAMP EXPANSION STA. 52+11.25 TO STA. 53+25
32	PROPOSED CROSS-SECTIONS FOR RAMP EXPANSION STA. 53+50 TO STA. 54+20

MACOMB MUNICIPAL AIRPORT
MACOMB, ILLINOIS

ILL. PROJECT No.: 08A0004D_0800
 Filename: R-002FLP.DWG
 Scale: NOT TO SCALE
 Date: 02/18/08

LAYOUT	RAW	02/18/08
DRAWN	BAK	02/18/08
REVIEWED	CAH	04/24/08



CONSTRUCT
RAMP EXPANSION
SUMMARY OF QUANTITIES
AND
INDEX TO SHEETS

APR 24, 2008 4:22 PM WALLE00723
I:\AIRPORTS\MACOMB\08A0004D\DESIGN\CADD\SHEETS\R-002FLP.DWG - Layout1

IL PROJ.: MGB-3798 A.I.P. PROJ.: 3-17-0064-B16