

MP004

DATE	REVISION	BY
05/14/08	REVISED AS PER I.D.A. REVIEW	CAH

SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AR108158	1/C #8 5KV UG CABLE IN UD	L.F.	5,428	
AR109200	INSTALL ELECTRICAL EQUIPMENT	L.S.	1	
AR110014	4" DIRECTIONAL BORE	L.F.	180	
AR110502	2-WAY CONCRETE ENCASED DUCT	L.F.	43	
AR110550	SPLIT DUCT	L.F.	112	
AR125410	MITL- STAKE MOUNTED	EACH	23	
AR125415	MITL- BASE MOUNTED	EACH	3	
AR125444	TAXI GUIDANCE SIGN, 4 CHARACTER	EACH	1	
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR150540	HAUL ROUTE	L.S.	1	
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	4,560	
AR155540	BY-PRODUCT LIME	TON	171	
AR155616	SOIL PROCESSING - 16"	S.Y.	4,698	
AR156510	SILT FENCE	L.F.	350	
AR156511	DITCH CHECK	EACH	3	
AR156521	HEADWALL PROTECTION	EACH	1	
AR156530	TEMPORARY SEEDING	ACRE	4	
AR201610	BITUMINOUS BASE COURSE	TON	680	
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	1,616	
AR401610	BITUMINOUS SURFACE COURSE	TON	402	
AR401900	REMOVE BITUMINOUS PAVEMENT	S.Y.	1,216	
AR602510	BITUMINOUS PRIME COAT	GAL	1,372	
AR603510	BITUMINOUS TACK COAT	GAL	678	
AR620520	PAVEMENT MARKING - WATERBORNE	S.F.	1,736	
AR620900	PAVEMENT MARKING REMOVAL	S.F.	114	
AR701515	15" RCP, CLASS IV	L.F.	80	
AR752415	PRECAST REINFORCED CONC. FES 15"	EACH	2	
AR800401	ADD 1 MODULE WITH SIGN BASE EXTENSION	EACH	1	
AR901510	SEEDING	ACRE	4	
AR908510	MULCHING	ACRE	4	

INDEX TO SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES AND INDEX TO SHEETS
3	PROPOSED SAFETY PLAN
4	PROPOSED CONSTRUCTION PLAN
5	PROPOSED CONSTRUCTION PLAN NOTES
6	PROPOSED PAVEMENT PREPARATION PLAN
7	PROPOSED STORM WATER POLLUTION PREVENTION PLAN
8	PROPOSED STORM WATER POLLUTION PREVENTION DETAILS
9	PROPOSED TAXIWAY "A" PLAN AND PROFILE
10	PROPOSED DRAINAGE PLAN
11	PROPOSED STAKING PLAN
12	PROPOSED MARKING PLAN
13	EXISTING ELECTRICAL PLAN STA. 108+00 TO STA. 121+00
14	EXISTING ELECTRICAL PLAN STA. 121+00 TO STA. 135+00
15	EXISTING AIRPORT VAULT SITE PLAN
16	PROPOSED ELECTRICAL PLAN STA. 108+00 TO STA. 121+00
17	PROPOSED ELECTRICAL PLAN STA. 121+00 TO STA. 135+00
18	PROPOSED ELECTRICAL PLAN HOMERUNS
19	ELECTRICAL LEGEND AND ABBREVIATIONS
20	NEW ELECTRICAL ONE LINE DIAGRAM FOR VAULT
21	AIRFIELD LIGHTING WIRING SCHEMATIC
22	HIGH VOLTAGE WIRING SCHEMATIC
23	VAULT FLOOR PLAN AND ELEVATIONS
24	LEGEND PLATE SCHEDULE AND GROUNDING DETAILS
25	PROPOSED ELECTRICAL DETAILS SHEET 1
26	PROPOSED ELECTRICAL DETAILS SHEET 2
27	PROPOSED ELECTRICAL DETAILS SHEET 3
28	ELECTRICAL NOTES SHEET 1
29	ELECTRICAL NOTES SHEET 2
30	TAXIWAY "A" CROSS-SECTIONS STA. 125+65 TO STA. 127+00
31	TAXIWAY "A" CROSS-SECTIONS STA. 127+50 TO STA. 128+50
32	TAXIWAY "A" CROSS-SECTIONS STA. 129+00 TO STA. 130+50
30	TAXIWAY "A" CROSS-SECTIONS STA. 131+00 TO STA. 132+50
31	TAXIWAY "A" CROSS-SECTIONS STA. 133+00 TO STA. 134+50
32	TAXIWAY "A" CROSS-SECTIONS STA. 134+75 TO STA. 135+00

METROPOLIS MUNICIPAL AIRPORT
METROPOLIS, ILLINOIS

H/I Project No. 07A01280_0800 Filename: R-002ELP.DWG Scale: N/A Date: 11/29/07	LAYOUT: MDR 11/29/07 DRAWN: MDR 11/29/07 REVIEWED: CAH 03/18/08
---	---



PROPOSED PARTIAL
PARALLEL TAXIWAY
SUMMARY OF QUANTITIES
AND
INDEX TO SHEETS

MAY 15, 2008 1:15 AM HAGL000382
I:\AIRPORTS\METROPOLIS\07A0128\CAD\SHEETS\R-002ELP.DWG - Layout1

IL PROJ.: M30-3760 A.I.P. PROJ.: 3-17-0067-B9