OVERLAY AIRCRAFT PARKING APRON

SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR150540	HAUL ROUTE	L.S.	1	
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	10	
AR156531	EROSION CONTROL BLANKET	S.Y.	1,192	
AR201610	BITUMINOUS BASE COURSE	TON	692	
AR401610	BITUMINOUS SURFACE COURSE	TON	411	
AR401655	BUTT JOINT CONSTRUCTION	S.Y.	150	
AR401900	REMOVE BITUMINOUS PAVEMENT	S.Y.	306	
AR501507	7" PCC PAVEMENT	S.Y.	302	
AR501600	PCC SIDEWALK	S.F.	332	
AR501900	REMOVE PCC PAVEMENT	S.Y.	88	
AR510510	TIE DOWN	EACH	9	
AR510900	REMOVE TIE DOWN	EACH	18	
AR602510	BITUMINOUS PRIME COAT	GAL.	49	
AR603510	BITUMINOUS TACK COAT	GAL.	1,427	
AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	246	
AR625510	TAR EMULSION SEAL COAT	S.Y.	415	
AR701212	12" CMP	L.F.	168	
AR751051	SLOTTED DRAIN	L.F.	50	
AR751414	INLET-TYPE D	EACH	1	
AR752212	METAL END SECTION 12"	EACH	1	
AR800465	DECORATIVE ROCK	S.Y.	20	
AR901510	SEEDING	ACRE	0.25	

DATE	REVISION	BY

ROBERT F. TRACY MUNICIPAL AIRPORT
MT. STERLING, ILLINOIS

IL. PROJ.: I63-3715 A.I.P. PROJ.: 3-17-0147-89

HSI Project No. 07A0058D 0800
Filename R-004FLP.DWG
Scale NOT TO SCALE
Date 11/30/07

LAYOUT	KDM	11/30/07
DRAWN	BAK	11/30/07
REVIEWED	CAH	04/14/08

HANSON

Hanson Professional Services Inc.
1525 South Sixth Street
Springfield, Illinois 62703-2886
Offices Nationwide

EXPAND AUTO PARKING LOT & OVERLAY APRON

SUMMARY OF QUANTITIES FOR OVERLAYING AIRCRAFT PARKING APRON

MAY 11, 2008 5:06 PM HAGLO00382
I:\AIRPORTS\MTSTERLING\07A0058\CAD\SHEETS\R-004FLP.DWG - Layout1