

REMOVE BITUMINOUS PAVEMENT

THE AREAS DESIGNATED AS [Hatched Pattern] ON THIS SHEET WILL HAVE THE EXISTING PAVEMENT REMOVED (FULL DEPTH) TO THE EXISTING ROCK SUBGRADE. ALL REMOVED MATERIAL WILL BE DISPOSED OF OFF THE AIRPORT SITE.

WHERE THE PROPOSED REMOVAL AREA ABUTS THE EXISTING PAVEMENT, THE PAVEMENT WILL BE SAWS AS SHOWN ON THIS SHEET. THIS 6" CUTOFF IS INCLUDED IN THE PAVEMENT REMOVAL QUANTITY. THE SAWING WILL BE CONSIDERED AS AN INCIDENTAL ITEM TO THE PROPOSED PAVEMENT REMOVAL AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

ANY ADJACENT PAVEMENT DAMAGED BY THE PAVEMENT REMOVAL OPERATIONS WILL BE REPAIRED AT THE CONTRACTOR'S OWN EXPENSE.

THIS ITEM OF WORK SHALL BE PAID FOR UNDER ITEM:
AR401900 "REMOVE BITUMINOUS PAVEMENT" - PER S.Y.

REMOVE AND REPLACE CLASS E FENCE NOTES

TO ASSIST THE CONTRACTOR IN COMPLETING THE EARTH SHOULDERING ADJACENT TO THE PROPOSED PARKING LOT EXPANSION, THE EXISTING FENCE ALONG THE EAST SIDE OF THE PROPOSED IMPROVEMENTS WILL BE REMOVED.

THE CONTRACTOR WILL STORE THE REMOVED FENCING UNTIL THE EARTH SHOULDERS HAVE BEEN COMPLETED. HE WILL THEN REPLACE THE FENCING IN THE SAME LOCATION FROM WHICH HE REMOVED IT.

ALL AREAS DISTURBED THAT ARE OUTSIDE OF THE PROPOSED SEEDING LIMITS WILL BE LIMED, FERTILIZED AND SEEDING IN ACCORDANCE WITH ITEM 901 "SEEDING". THIS WORK WILL BE CONSIDERED AS AN INCIDENTAL ITEM TO THE PROPOSED FENCE RELOCATION AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

THIS ITEM OF WORK WILL BE PAID FOR UNDER ITEM:
AR162960 RELOCATE CLASS E FENCE -- PER L.F.

DUCT EXTENSION NOTES

THE EXISTING DUCT SHOWN ON THIS SHEET WILL BE EXTENDED TO A MINIMUM OF 2' BEYOND THE PROPOSED PAVEMENT EDGE.

THE EXISTING CABLE INSIDE THE DUCTS SHALL REMAIN IN PLACE AND FUNCTIONING DURING THE EXTENSION.


THE CONTRACTOR WILL USE 3" SPLIT PVC DUCT TO EXTEND THE EXISTING DUCTS.

THE CONTRACTOR WILL ENCASE THE DUCTS WITH CONCRETE A MINIMUM OF 4" ON ALL SIDES AFTER THEY HAVE BEEN EXTENDED AS SHOWN IN DETAIL.

THE DUCT EXTENSION WILL BE PAID FOR UNDER THE FOLLOWING ITEM:
AR110551 "EXTEND DUCT" _____ PER L.F.

LEGEND

- [White Box] EXISTING PAVEMENT
- [Grey Box] PROPOSED IMPROVEMENTS
- [Black Box] EXISTING VAULT
- [Hatched Box] PROPOSED PAVEMENT REMOVAL
- [Dashed Line] EXISTING FENCE (TO REMAIN)
- [Solid Line with Circle] EXISTING FENCE (TO BE REMOVED AND REPLACED)
- [Dashed Line with Arrow] EXISTING DITCH
- [Line with E] EXISTING ELECTRICAL CABLE
- [Double Line] EXISTING DUCT
- [Double Line with Dashed] PROPOSED DUCT EXTENSION



BY		
DATE	REVISION	
ROBERT F. TRACY MUNICIPAL AIRPORT MT. STERLING, ILLINOIS		
IL PROJ.: 163-3715		A.I.P. PROJ.: 3-17-0147-B9
I&L Project No. 07A0058D_0800 Filename: R-112PRP.DWG Scale: 1" = 10' Date: 12/03/07	LAYOUT: KDM 12/03/07 DRAWN: BAK 12/03/07 REVIEWED: CAH 4/14/08	<p>Hanson Professional Services Inc. 1525 South Sixth Street Springfield, Illinois 62703-2886 Offices Nationwide</p>
EXPAND AUTO PARKING LOT & OVERLAY APRON		
PROPOSED PAVEMENT PREPARATION PLAN FOR AUTO PARKING LOT		
19		
19 of 25 sheets		