

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	LOCATION					
				SN-098	SN-101	SN-104	SN-126	SN-141	SN-147
				2C081I080L003.3	2S081I088R015.3	2S081I088L016.0	2S081S005R011.2	2C081S092R029.3	2S081S092L028.0
25000300	SEEDING, CLASS 3	ACRE	.5	0.05	0.10	0.10	0.10	0.05	0.10
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	45	4.5	9	9	9	4.5	9
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	45	4.5	9	9	9	4.5	9
25100630	EROSION CONTROL BLANKET	SQ YD	2420	242	484	484	484	242	484
28000305	TEMPORARY DITCH CHECKS	FOOT	185		21	134			30
28000400	PERIMETER EROSION BARRIER	FOOT	533	156			173	70	134
28000500	INLET AND PIPE PROTECTION	EACH	1						1.0
28000510	INLET FILTERS	EACH	2						2.0
44001980	CONCRETE BARRIER REMOVAL	FOOT	74				74		
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	6.2			3.6		2.6	
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	537.5		212.5			37.5	287.5
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	3		2.0				1.0
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4		2.0			2.0	
63200310	GUARDRAIL REMOVAL	FOOT	600		250.0			50.0	300.0
63700255	CONCRETE BARRIER, DOUBLE FACE, 32 INCH HEIGHT	FOOT	75				75		
67100100	MOBILIZATION	L SUM	1	0.17	0.16	0.17	0.17	0.17	0.17
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	10		2	3	2	1	2
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	0.16	0.16	0.17	0.17	0.17	0.17
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	4	1	1		1		1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	0.17	0.17	0.17	0.17	0.17	0.17
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1	0.16	0.16	0.17	0.17	0.17	0.17
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	0.16	0.16	0.17	0.17	0.17	0.17
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	13000		2600	3900	2600	1300	2600
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4335		867	1300	867	434	867
70400100	TEMPORARY CONCRETE BARRIER	FOOT	900				300		600
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	462.5		462.5				
70600250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4				2		2
70600350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2				
72000200	SIGN PANEL - TYPE 2	SQ FT	24		24				
72000300	SIGN PANEL - TYPE 3	SQ FT	2148	215.75	506.25	393.75	506.25	104.0	421.25
73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4'-0" X 4'-6")	FOOT	269			97	90		82
73300200	OVERHEAD SIGN STRUCTURE - SPAN, TYPE II-A (4'-6" X 5'-3")	FOOT	101		101				
73301810	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	229.8	20.3	54.4	39.7	45.3	18.1	52

HBM
ENGINEERING GROUP, LLC
CONSULTING & DESIGN
INSPECTION & TESTING
RESEARCH & TESTING

4415 WEST HARRISON ST.
SUITE 231
HILLSIDE, IL 60162
PHONE: (708) 236-0900
FAX: (708) 236-0901

USER NAME =
DESIGNED - JMG
CHECKED - JJS
DRAWN - AI
PLOT SCALE =
PLOT DATE = 3/12/2014

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES (SHEET 1 OF 2)

Sheet No. 1 of 2

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.		ROCK ISLAND	45	5
* D-2 OVD SIN STR REPL 14-26		CONTRACT NO. 46287		
ILLINOIS FED. AID PROJECT				