


NOTES:

- 1) INSTALL TEMPORARY DITCH CHECKS AS DIRECTED BY THE ENGINEER.
- 2) INSTALL IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3.
- 3) RELOCATE 212.5' OF TEMPORARY CONCRETE BARRIER TO WESTBOUND IL 5/IL 92 AND RELOCATE 250' OF TEMPORARY CONCRETE BARRIER TO EASTBOUND IL 5/IL 92.
- 4) REMOVE EXISTING WESTBOUND MEDIAN GUARDRAIL.
- 5) INSTALL 100 FT OF GUARDRAIL STARTING 12.5 FT WEST OF THE EAST END OF SIGN FOUNDATION AND 16 FT FROM THE EDGE OF PAVEMENT.
- 6) INSTALL TRAFFIC BARRIER TERMINAL, TYPE 2 TO PROPOSED WESTBOUND MEDIAN GUARDRAIL.
- 7) INSTALL TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT TO PROPOSED WESTBOUND MEDIAN GUARDRAIL.
- 8) REMOVE EXISTING EASTBOUND MEDIAN GUARDRAIL.
- 9) INSTALL 112.5 FT OF STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS ENDING 12.5 FT EAST OF THE WESTERN EDGE OF THE SIGN STRUCTURE FOUNDATION AND 12 FT FROM THE EDGE OF PAVEMENT.
- 10) INSTALL TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT TO PROPOSED EASTBOUND MEDIAN GUARDRAIL.
- 11) INSTALL TRAFFIC BARRIER TERMINAL, TYPE 2 TO PROPOSED EASTBOUND MEDIAN GUARDRAIL.
- 12) REMOVE TEMPORARY CONCRETE BARRIER AND IMPACT ATTENUATORS ONCE STEEL PLATE BEAM GUARDRAIL AND TRAFFIC BARRIER TERMINALS ARE INSTALLED AND ACCEPTED BY THE ENGINEER.



ENGINEERING CONSULTANT
 **Ciorba Group, Inc.**
 CONSULTING ENGINEERS
 8007 North Cumberland Avenue, Suite 402
 Chicago, Illinois 60656
 Tel. 773.775.4009 Fax 773.775.4014
 Email: chicago@ciorba.com

USER NAME = untitled	DESIGNED - JPA	REVISED -
	DRAWN - JPA	REVISED -
PLOT SCALE = 40,0000' / in.	CHECKED - MJL	REVISED -
PLOT DATE = 3/12/2014	DATE -	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**SIGN STRUCTURE REPLACEMENT
 ROADWAY PLAN DETAIL - SN-101**

SCALE: 1" = 20' SHEET NO. 2 OF 6 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	.	**	45	8
D-2 OVD SIN STR REPL 14-26			CONTRACT NO. 46287	
ILLINOIS FED. AID PROJECT				

K:\Ciorba\pen table\Files to print\0546287-sht-plan-002.dgn