



NOTES:

- 1) INSTALL TEMPORARY DITCH CHECKS, PERIMETER EROSION BARRIER, INLET AND PIPE PROTECTION AS DIRECTED BY THE ENGINEER.
- 2) INSTALL IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3.
- 3) INSTALL 300' OF TEMPORARY CONCRETE BARRIER ON WESTBOUND IL 92 AND 300' OF TEMPORARY CONCRETE BARRIER ON EASTBOUND IL 92.
- 4) REMOVE EXISTING WESTBOUND TRAFFIC BARRIER TERMINAL, TYPE 2 ALONG MEDIAN.
- 5) INSTALL 75 FT OF GUARDRAIL ATTACHING TO EXISTING WESTBOUND MEDIAN GUARDRAIL. MAINTAIN EXISTING TAPER UNTIL 10 FT FROM EDGE OF PAVEMENT.
- 6) INSTALL TRAFFIC BARRIER TERMINAL, TYPE 2, TO PROPOSED SOUTHBOUND MEDIAN GUARDRAIL.
- 7) EXISTING WESTBOUND OUTSIDE GUARDRAIL TO REMAIN
- 8) REMOVE EXISTING EASTBOUND MEDIAN GUARDRAIL.
- 9) INSTALL 312.5 FT OF GUARDRAIL ATTACHING TO EXISTING GUARDRAIL, TYPE D.
- 10) TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT TO PROPOSED EASTBOUND MEDIAN GUARDRAIL.
- 11) RELOCATE TEMPORARY CONCRETE BARRIER AND IMPACT ATTENUATORS ONCE STEEL PLATE BEAM GUARDRAIL AND TRAFFIC BARRIER TERMINALS ARE INSTALLED AND ACCEPTED BY THE ENGINEER.



	ENGINEERING CONSULTANT	USER NAME = untitled	DESIGNED - JPA	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SIGN STRUCTURE REPLACEMENT ROADWAY PLAN DETAIL - SN-147	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	Ciorba Group, Inc. CONSULTING ENGINEERS 8007 North Cumberland Avenue, Suite 402 Chicago, Illinois 60625 Tel. 773.775.4009 Fax 773.775.4014 Email: cigrpa@ciorba.com	DRAWN - JPA CHECKED - MJL DATE -	REVISED - REVISED - REVISED -	SCALE: 1" = 20' SHEET NO. 6 OF 6 SHEETS STA. TO STA.			VAR. D-2 OVD SIN STR REPL 14-26 ILLINOIS FED. AID PROJECT	** CONTRACT NO. 46287	45 12	**ROCK ISLAND & HENRY	

K:\Ciorba\pen table\Files to print\0546287-sht-plan-006.dgn