

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				PEORIA	KNOX	TAZEWELL
				100% STATE 0040	100% STATE 0040	100% STATE 0040
67100100	MOBILIZATION	L SUM	1	0.34	0.33	0.33
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	20	8	4	8
70100315	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	EACH	1	1		
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	19	9	3	7
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1			1
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1		1	
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1			1
72000300	SIGN PANEL - TYPE 3	SQ FT	4302.3	2760.5	173.3	1368.5
72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	4795.5	3197.5	294.5	1303.5
73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4' -0" X 4' -6")	FOOT	554	426		128
73300200	OVERHEAD SIGN STRUCTURE - SPAN, TYPE II-A (4' -6" X 5' -3")	FOOT	247			247
73301810	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	441.5	238.2		203.3
73301840	OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A	FOOT	51	34	17	
73302170	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (36" X 5' -6")	FOOT	50	50		

FILE NAME : overhead sign plans.dgn	USER NAME : davis	DESIGNED - DRAWN -	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLT SCALE : 3/32, 7/888 / in.	CHECKED -	REVISED -	VAR			D4-4 DVD SIN STR REPL 14-4T	VAR	65	2	
PLT DATE : 3/21/2014	DATE -	REVISED -	CONTRACT NO. 46314			ILLINOIS FED. AID PROJECT				