URBAN

	SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005					
*	78000100	THERMOPLASTIC PAVEMENT MARKING -	SQ FT	182	182					
		LETTERS AND SYMBOLS								
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	52034	52034					
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	769	769					
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	264	264					
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	59	59					
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	350	350					
	78300200	RAISED REFLECTIVE PAVEMENT MARKER	EACH	320	320					
		REMOVAL								
*	88600600	DETECTOR LOOP REPLACEMENT	FOOT	54	54					
	X2020110	GRADING AND SHAPING SHOULDERS	UNIT	340	340					
	X4060110	BITUMINOUS MATERIALS (PRIME COAT)	POUND	40,796	40,796					
	X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	20	20					
	X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	2	2					
	Z0004562	COMBINATION CONCRETE CURB AND GUTTER	FOOT	30	30					
		REMOVAL AND REPLACEMENT								
14	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					

	SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005					

* Specialty Items

Rev.

FILE NAME = c:\pw_work\pwidot\paryroot\d0383085\D225it-st-plan.dgn	USER NAME = paryroot	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 4/4/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

U.S. ROUTE 52 (COUGAR ROAD – 0.1 MI W/O 2nd STREET)
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
852	18-RS-6	WILL	26	4
		CONTRACT NO. 60N08		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		