

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE																
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0004 90% FED 10% STATE STATE URBAN	0021 90% FED 10% STATE TRAFFIC SIGNALS	0014 90% FED 10% STATE BRIDGE; MEDIAN WORK	0040 90% FED 10% STATE RETAINING WALL	0028 80% STATE 20% WILLOW SPRINGS SHARED PATH SIDEWALK	0021 100% WILLOW SPRINGS EVP											
25200200	SUPPLEMENTAL WATERING	UNIT	45	45																
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	81	81																
28000305	TEMPORARY DITCH CHECKS	FOOT	84	84																
28000400	PERIMETER EROSION BARRIER	FOOT	1760	1760																
28000510	INLET FILTERS	EACH	43	43																
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	141	141																
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	1763	1763																
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	1673					1673												
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	993	993																
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	670	670																
X4060110	BITUMINOUS MATERIALS (PRIME COAT)	POUND	9251	9251																
<del>40600300</del>	<del>AGGREGATE (PRIME COAT)</del>	<del>TON</del>	<del>17</del>	<del>17</del>																
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	3	3																
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	528	528																

Rev.