

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE																	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN																
				0004 90% FED 10% STATE STATE URBAN	0021 90% FED 10% STATE TRAFFIC SIGNALS	0014 90% FED 10% STATE BRIDGE/ MEDIAN WORK	0040 90% FED 10% STATE RETAINING WALL	0028 80% STATE 20% WILLOW SPRINGS SHARED PATH SIDEWALK	0021 100% WILLOW SPRINGS EVP											
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	25	25																
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	185	185																
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	5	5																
60100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1																
50102400	CONCRETE REMOVAL	CU YD	38.5	5.5			33													
50157300	PROTECTIVE SHIELD	SQ YD	2320				2320													
50200100	STRUCTURE EXCAVATION	CU YD	80				80													
50300225	CONCRETE STRUCTURES	CU YD	145				145													
50300255	CONCRETE SUPERSTRUCTURE	CU YD	33			33														
50300260	BRIDGE DECK GROOVING	SQ YD	268			268														
50300285	FORM LINER TEXTURED SURFACE	SQ FT	3166				3166													
50300300	PROTECTIVE COAT	SO YD	469			469														
50500505	STUD SHEAR CONNECTORS	EACH	438				438													
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	16130			4430	11700													
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	478	478																
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	139	139																

15

Rev.

FILE NAME :	USER NAME :	DESIGNED :	REVISED :	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES IL 171 (ARCHER AVE) AT 104TH AVE. (FLAVIN ROAD)				F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN :	REVISED :		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT
		CHECKED :	REVISED :								COOK	129	6
		DATE :	REVISED :									CONTRACT NO. 60T24	