

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE																
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0004 90% FED 10% STATE STATE URBAN	0021 90% FED 10% STATE TRAFFIC SIGNALS	0014 90% FED 10% STATE BRIDGE, MEDIAN WORK	0040 90% FED 10% STATE RETAINING WALL	0028 80% STATE 20% WILLOW SPRINGS SHARED PATH SIDEWALK	0021 100% WILLOW SPRINGS EVP											
X7030055	WET REFLECTIVE TEMPORARY TAPE TYPE III, 24 INCH	FOOT	240	240																
* X8570226	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1		1															
* X8620200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	EACH	1		1															
* X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	803		803															
Z0006016	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 3/4 INCHES	SQ YD	290			290														
* Z0007118	UNTREATED TIMBER LAGGING	SQ FT	2743				2743													
Z0012146	BRIDGE DECK SCARIFICATION 2 3/4"	SQ YD	290			290														
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1																
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	13			13														
Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	10			10														
Z0026404	FURNISHING SOLDIER PILES (W SECTION)	FOOT	1623				1623													
Z0026407	TEMPORARY SHEET PILING	SQ FT	400				400													
Ø Z0076600	TRAINEES	HOOR	1000	1000																
Ø Z0076604	TRAINEES - TRAINING PROGRAM GRADUATE	HOOR	1000	1000																

FILE NAME =	USER NAME =	DESIGNED -	REVISED -
DATE =		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
IL 171 (ARCHER AVE) AT 104TH AVE. (FLAVIN ROAD)			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3565	B-H-5	COOK	129	17
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60T24	

Ø 0042

* Specialty Items