

NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN (1) WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL 2 SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

FILE NAME :	USER NAME = steedpa	DESIGNED -	REVISED - R. MIRS 09-15-97			FAP COTTON TOTAL SHEET
c:\pw_work\pwidot\steadpa\d0329923\Dist	td.dgn	DRAWN -	REVISED - R. MIRS 12-11-97	STATE OF ILLINOIS	ARTERIAL ROAD	RTE. SECTION COUNTY SHEETS NO.
	PLOT SCALE = 100.0000 ' / in.	CHECKED ~	REVISED -T. RAMMACHER 02-02-99		INFORMATION SIGN	557 2013-048I KANE 24 24
	PLOT DATE : 3/20/2014	DATE -	REVISED - C. JUCIUS 01-31-07	2 of Inditor official	SCALE: NONE SHEET NO. ! OF 1 SHEETS STA. TO STA.	TC-22 CONTRACT NO. 60X02