

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE																		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	90% FED 10% STATE	90% FED 5% STATE 5% RIVERSIDE	100% RIVERSIDE	90% FED 10% STATE	80% STATE 20% RIVERSIDE	90% FED 10% STATE	100% RIVERSIDE											
				ROADWAY 0005	TR. SIGNALS 0021	E.V.P. 0021	COMBINATION LIGHTING 0021	SHARED-USE PATH AND SIDEWALK 0028	INTERCONNECT 0021	UTILITIES 0043											
* 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	10		10																
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	11		11																
* 88600100	DETECTOR LOOP, TYPE I	FOOT	910		910																
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	8		8																
* 89501400	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, DETECTOR UNIT	EACH	2			2															
* 89501410	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT	EACH	1			1															
* 89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	1		1																
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	5000						5000												
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1																
* 89502380	REMOVE EXISTING HANDHOLE	EACH	8		8																
* 89502382	REMOVE EXISTING DOUBLE HANDHOLE	EACH	1		1																
* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	9		9																
X0322917	PROPOSED STORM SEWER CONNECTION TO EXISTING MANHOLE	EACH	3	3																	
											* SPECIALTY ITEMS										

13