SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		0005					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	170	170					
25200110	SODDING, SALT TOLERANT	SQ YD	170	170					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	48	48					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1544	1544					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	368	368					
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	354	354					
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	3153	3153					
42001300	PROTECTIVE COAT	SQ YD	266	266					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	28752	28752					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	30	30					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	5	5					
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	30	30					

13

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		0005					
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	30	30					
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	5	5					
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	30	30					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	370	370					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1	1					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
67100100	MOBILIZATION	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	895	895					
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	109.2	109.2					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2584.8	2584.8					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	380	380					
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	101	101					

14

FILE NAME = c:\pw_work\pwidot\bakermd\d0382964\D258814-sht-plan.dgn	USER NAME = Bakerom	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 3/27/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

WASHINGTON STREET – BRIGGS ST TO U.S. 30 (LINCOLN HIGHWAY)
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0307	31RS-1	WILL	23	3

CONTRACT NO. 60Y04

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT