ROUTE: IL 68 /Dundee Rd (Wolf Road to Waukegan Road(IL 43)) (Continued)

CROSS STREET		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD)
		WB	1	12	3	36	4
		WB	1	12	3	36	4
		WB	1	12	3	36	4
		WB	1	12	3	36	4
		WB	1	12	3	36	4
		WB	2	12	3	36	4
		WB	2	12	3	36	4
		WB	2	12	6	72	8
		WB	2	12	3	36	4
		WB	2	12	6	72	8
		WB	2	12	3	36	4
		WB	2	12	3	36	4
		WB	2	12	3	36	4
		WB	2	12	6	72	8
		WB	2	12	6	72	8
		WB	2	12	3	36	4
		WB	2	12	3	36	4
		WB	2	12	3	36	4
		WB	2	12	3	36	4
	Pfingsten Road	WB	2	12	3	36	4
Pfingsten Road		WB	1	12	3	36	4
		WB	1	12	3	36	4
		WB	1	12	3	36	4
		WB	1	12	3	36	4
		WB	2	12	3	36	4
		WB	2	12	6	72	8
		WB	2	12	3	36	4
		WB	2	12	3	36	4
	Anthony Trail	WB	2	12	3	36	4
Anthony Trail		WB	1	12	3	36	4
		WB	1	12	4	48	5
		WB	1	12	3	36	4
		WB	1	12	3	36	4
		WB	1	12	3	36	4
		WB	2	12	3	36	4
		WB	2	12	3	36	4
		WB	2	12	4	48	5
		WB	2	12	10	120	13
	Landwehr Road	WB	2	12	4	48	5
Landwehr Road		WB	1	12	3	36	4
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	3	36	4
		WB	1	12	3	36	4
		WB	1	12	4	48	5
		WB	1	12	3	36	4
		WB	1	12	3	36	4
		WB	1	12	3	36	4
		WB	1	12	3	36	4
		WB	2	12	3	36	4

ROUTE: IL 68 /Dundee Rd (Wolf Road to Waukegan Road(IL 43)) (Continued)

CROSS STREET		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD)
		WB	2	12	4	48	5
		WB	2	12	3	36	4
		WB	2	12	4	48	5
		WB	2	12	3	36	4
		WB	2	12	3	36	4
		WB	2	12	3	36	4
		WB	2	12	4	48	5
		WB	2	12	3	36	4
	Huehl Road	WB	2	12	3	36	4
Huehl Road		WB	1	12	3	36	4
		WB	1	12	3	36	4
		WB	1	12	6	72	8
		WB	1	12	3	36	4
		WB	1	12	3	36	4
		WB	1	12	10	120	13
		WB	1	12	3	36	4
		WB	1	12	6	72	8
		WB	2	12	3	36	4
		WB	2	12	6	72	8
		WB	2	12	6	72	8
		WB	2	12	10	120	13
		WB	2	12	3	36	4
		WB	2	12	3	36	4
		WB	2	12	10	120	13
		WB	2	12	3	36	4
	Charlemagne Drive	WB	2	12	6	72	8
Charlemagne Drive		WB	1	12	3	36	4
		WB	1	12	6	72	8
		WB	1	12	3	36	4
		WB	1	12	6	72	8
		WB	1	12	3	36	4
		WB	1	12	3	36	4
		WB	1	12	12	144	16
		WB	1	12	8	96	10
		WB	1	12	3	36	4
		WB	1	12	3	36	4
		WB	1	12	3	36	4
		WB	1/2	3	50	150	16
		WB	2	12	3	36	4
		WB	2	12	3	36	4
		WB	2	12	6	72	8
		WB	2	12	8	96	10
		WB	2	12	3	36	4
		WB	2	12	3	36	4
		WB	2	12	10	120	13
		WB	2	12	3	36	4
		WB	2	12	3	36	4
		WB	2	12	3	36	4
		WB	2	12	3	36	4
		WB	2	12	3	36	4

CONTINUED ON NEXT SHEET

FILE NAME =	USER NAME = Aumm	DESIGNED -	REVISED -
c:\pw_work\pwidot\aumm\d0382486\HMA-Cook-North.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
Default	PLOT DATE = 4/4/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

INTERMITTENT RESURFACING SCHEDULE
IL 68 /DUNDEE RD

SCALE: | SHEET OF SHEETS | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2014-020RS	COOK	74	9
		CONTRACT NO. 60Y06		
	ILLINOIS FED. AID PROJECT			