ROUTE: Milwaukee Avenue/ IL 21(Dear Love Road to Golf Road/IL 58) (Continued)

CROSS STREET		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD)
	Greenwood Avenue	SB	3	12	3	36	4
Greenwood Avenue		SB	1	12	6	72	8
		SB	1	12	6	72	8
		SB	1	12	6	72	8
		SB	1/2	3	100	300	33
		SB	2	12	6	72	8
		SB	2	12	6	72	8
	Golf Road/IL 58	SB	3	12	6	72	8
Golf Road/IL 58		NB	3	12	3	36	4
		NB	3	12	3	36	4
		NB	3	12	3	36	4
		NB	3	12	3	36	4
		NB	3	12	4	48	5
		NB	2	12	3	36	4
		NB	2	12	3	36	4
		NB	2	12	4	48	5
		NB	1/2	3	50	150	16
	Greenwood Avenue	NB	1/2	3	50	150	16
Greenwood Avenue		NB	3	12	3	36	4
		NB	2	12	3	36	4
		NB	2	12	3	36	4
		NB	2	12	3	36	4
		NB	2	12	3	36	4
		NB	2	12	3	36	4
		NB	2	12	4	48	5
		NB	2	12	8	96	10
		NB	2	12	3	36	4
		NB	1/2	3	20	60	6
		NB	1/2	3	30	90	10
		NB	1/2	3	50	150	16
		NB	1/2	3	20	60	6
		NB	1/2	4	20	80	8
		NB	1/2	4	50	200	22
		NB	1/2	3	25	75	8
		NB	1/2	3	100	300	33
		NB	1/2	3	30	90	10
		NB	1/2	3	30	90	10
		NB	1	4	12	48	5
		NB	1	12	6	72	8
		NB	1	12	20	240	26
		NB	1	12	6	72	8
		NB	1	12	3	36	4
		NB	1	12	3	36	4
		NB	1	12	3	36	4
		NB	1	12	8	96	10
		NB	1	12	3	36	4

ROUTE: Milwaukee Avenue/ IL 21(Dear Love Road to Golf Road/IL 58) (Continued)

CROSS STREET		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD)
		NB	1	12	3	36	4
		NB	1	12	3	36	4
		NB	1	12	3	36	4
		NB	1	12	3	36	4
	Central Road	NB	1	12	3	36	4
Central Road		NB	2	6	20	120	13
		NB	2	12	3	36	4
		NB	2	12	3	36	4
		NB	2	12	5	60	6
		NB	2	12	3	36	4
		NB	2	12	4	48	5
		NB	2	12	3	36	4
		NB	2	12	3	36	4
		NB	2	12	3	36	4
		NB	2	12	3	36	4
		NB	2	12	3	36	4
		NB	2	10	6	60	6
		NB	2	12	10	120	13
		NB	2	12	3	36	4
		NB	2	12	3	36	4
		NB	2	12	15	180	20
		NB	2	12	3	36	4
		NB	2	12	3	36	4
		NB	2	12	3	36	4
		NB	2	12	3	36	4
		NB	2	12	3	36	4
		NB	2	12	3	36	4
		NB	1/2	3	100	300	33
		NB	1/2	3	50	150	16
		NB	1/2	3	100	300	33
		NB	1/2	3	100	300	33
		NB	1/2	3	100	300	33
		NB	1/2	3	100	300	33
		NB	1	12	3	36	4
		NB	1	12	3	36	4
		NB	1	12	3	36	4
		NB	1	12	3	36	4
		NB	1	12	10	120	13
		NB	1	12	3	36	4
		NB	1	12	3	36	4
		NB	1	12	3	36	4
		NB	1	12	3	36	4
		NB	1	12	3	36	4
		NB	1	12	3	36	4
		NB	1	12	3	36	4
		NB	1	12	3	36	4
		NB	1	12	3	36	4
		NB	1	12	3	36	4
	Dear Love Road	NB	1	12	3	36	4
		TOTALS:			**2379**		**1389**
					SF		**SY**

FILE NAME = c:\pw_work\pwidot\aumm\d0382486\HMA-Cook-North.dgn	USER NAME = Aumm	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
Default	PLOT DATE = 4/4/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

INTERMITTENT RESURFACING SCHEDULE
IL 21 /MILWAUKEE AVE

SCALE: | SHEET OF SHEETS | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2014-02ORS	COOK	74	13
		CONTRACT NO. 60Y06		
	ILLINOIS	FED. AID PROJECT		