ROUTE: River Road(Old Willow Road to Rand Road/US 12) (Continued)

CROSS STREET		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD)
		SB	2	4	30	120	13
		SB	1	12	4	48	5
		SB	1	13	4	52	6
		SB	1	13	4	52	6
		SB	1	13	4	52	6
		SB	1	12	4	48	5
		SB	2	12	4	48	5
		SB	1	12	4	48	5
		SB	2	12	4	48	5
		SB	2	6	121	726	81
		SB	1	4	50	200	22
		SB	1	12	10	120	13
		SB	2	12	10	120	13
		SB	1	12	12	144	16
		SB	2	12	8	96	11
		SB	1	12	6	72	8
		SB	1	12	3	36	4
		SB	1	12	6	72	8
		SB	1	12	20	240	27
		SB	1	15	5	75	8
		SB	LT	5	5	25	3
		SB	1	12	5	60	7
		SB	1,2	3	60	180	20
		SB	LT	11	6	66	7
		SB	1	12	6	72	8
		SB	1	13	6	78	9
		SB	LT	12	8	96	11
		SB	LT	12	4	48	5
		SB	1	12	4	48	5
		SB	2	12	4	48	5
		SB	2	9	3	27	3
	Euclid Avenue	SB	2	9	3	27	3
Euclid Avenue		SB	2	9	3	27	3
		SB	1,2	3	60	180	20
		SB	1	12	4	48	5
		SB	2	3	60	180	20
		SB	1	12	20	240	27
		SB	1	12	15	180	20
		SB	1	12	10	120	13
		SB	2	13	4	52	6
		SB	1	12	10	120	13
		SB	1	12	15	180	20
		SB	1	12	4	48	5
		SB	1	12	6	72	8
	Kensington Road	SB	1	12	7	84	9
Kensington Road		SB	1	12	15	180	20
		SB	1	12	15	180	20
		SB	1	12	6	72	8
		SB	1	12	6	72	8
		SB	1	12	4	48	5

ROUTE: River Road(Old Willow Road to Rand Road/US 12) (Continued)

CROSS STREET		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD)
		SB	2	12	4	48	5
		SB	1	12	4	48	5
		SB	2	13	4	52	6
		SB	1	12	4	48	5
		SB	2	12	4	48	5
		SB	1	12	6	72	8
		SB	1	12	4	48	5
		SB	2	12	4	48	5
		SB	1,2	3	70	210	23
		SB	1	13	4	52	6
	Central Road	SB	1,2	3	40	120	13
Central Road		SB	1,2	3	50	150	17
		SB	1	13	4	52	6
		SB	1,2	3	160	480	53
		SB	1	16	4	64	7
		SB	1	12	4	48	5
		SB	1	12	4	48	5
		SB	1	12	4	48	5
		SB	1,2	3	50	150	17
		SB	1	12	8	96	11
		SB	2	12	4	48	5
		SB	1,2	4	95	380	42
		SB	1	12	8	96	11
		SB	2	12	8	96	11
		SB	2	3	40	120	13
		SB	1,2	3	60	180	20
		SB	1	12	4	48	5
		SB	2	12	4	48	5
		SB	1	12	4	48	5
		SB	1	13	4	52	6
	PCC Joint N of Golf Road/IL 58	SB	1	12	6	72	8
PCC Joint S of Golf Road/IL 58		SB	1	13	4	52	6
		SB	1	12	4	48	5
		SB	2	12	4	48	5
		SB	2	12	6	72	8
		SB	1,2	3	12	36	4
		SB	2	14	7	98	11
		SB	1	12	4	48	5
		SB	1	14	56	784	87
		SB	2	12	7	84	9
		SB	1	12	8	96	11
		SB	1	12	8	96	11
		SB	2	12	6	72	8
		SB	1,2	13	4	52	6
		SB	2	4	20	80	9
		SB	2	13	20	260	29
		SB	1,2	3	70	210	23
	Rand Road/US 12	SB	2	9	15	135	15
		TOTALS:			**10998**		**6695**
					FT		**SY**

FILE NAME = c:\pw_work\pwidot\aumm\d0382486\HMA-Cook-North.dgn	USER NAME = Aumm	DESIGNED -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	DRAWN -	REVISED -
Default	PLOT DATE = 4/4/2014	CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

INTERMITTENT RESURFACING SCHEDULE
RIVER RD

SCALE: | SHEET OF SHEETS | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2014-02ORS	COOK	74	20
		CONTRACT NO. 60Y06		
		ILLINOIS FED. AID PROJECT		