ROUTE: IL 19 (Barrington Road to IL 59) (Continued)

CROSS STREET		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD)
		EB	2	12	6	72	8
		EB	1	12	6	72	8
		EB	1	12	50	600	67
		EB	2	12	6	72	8
	Vine Street	EB	1	12	150	1800	200
Vine Street		EB	1	12	250	3000	333
	Alexander Avenue		2	12	6	72	8
Alexander Avenue			2	6	50	300	33
			LT	12	250	3000	333
			1	12	250	3000	333
			2	12	25	300	33
			1	12	10	120	13
			1	12	10	120	13
	Shirley Avenue		2	6	50	300	33
Shirley Avenue			1	12	6	72	8
			1	12	8	96	11
			1	12	6	72	8
			1	12	6	72	8
			1	12	150	1800	200
			1	12	6	72	8
			1	12	6	72	8
			1	12	6	72	8
			1	12	6	72	8
			1/2	6	150	900	100
	McKool Avenue		2	12	6	72	8
McKool Avenue			1	6	400	2400	267
			2	6	400	2400	267
			2	6	250	1500	167
			MED	12	50	600	67
			LT	12	250	3000	333
	East Avenue		1	1	250	250	28
East Avenue			1	12	100	1200	133
			1	12	150	1800	200
			2	12	6	72	8
			1	12	600	7200	800
			MED	12	400	4800	533
			2	12	6	72	8
			2	12	6	72	8
			2	12	6	72	8
			1	12	250	3000	333
	Westview Plaza Entrance		LT	12	250	3000	333
Westview Plaza Entrance			2	12	6	72	8
	Barrington Road		2	6	100	600	67
		TOTALS:			**11020**		**12281**
					FT		**SY**

ROUTE: Bluff City Boulevard(US 20 to Gifford Road)

CROSS STREET		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD)
US20	Copart Entrance	WB	1				
Copart Entrance		WB	1	12	6	72	8
		WB	LT	12	6	72	8
	Waste Management Entrance	WB	1	14	10	140	16
Waste Management Entrance		WB	1	12	100	1200	133
	1260 Entrance	WB	1	6	100	600	67
1260 Entrance	East End Guard Rail	WB	1	6	50	300	33
East End Guard Rail	Gifford Road	WB	1	6	30	180	20
Gifford Road	Midwestern Auto Parts sign	EB	1				
Midwestern Auto Parts sign		EB	1	6	100	600	67
	East End Guard Rail	EB	1	12	10	120	13
East End Guard Rail	1260 Entrance	EB	1	6	50	300	33
1260 Entrance	Waste Management Entrance	EB	1	12	100	1200	133
Waste Management Entrance	Copart Entrance	EB	1	14	10	140	16
		TOTALS:			**572**		**547**
					FT		**SY**

FILE NAME =	USER NAME = Aumm	DESIGNED -	REVISED -
c:\pw_work\pwidot\aumm\d0382486\HMA-Cook-North.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
Default	PLOT DATE = 4/4/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

INTERMITTENT RESURFACING SCHEDULE
IL 19 AND BLUFF CITY BLVD

SCALE: | SHEET OF SHEETS | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2014-020RS	COOK	74	65
		CONTRACT NO. 60Y06		
	ILLINOIS	FED. AID PROJECT		