ROUTE: IL 25 (Stearns Road to Bartlett Road)

CROSS STREET FROM	CROSS STREET TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
Bartlett Road		SB	1	12	6	72	8
		SB	1	12	6	72	8
		SB	1	12	6	72	8
		SB	1	12	6	72	8
		SB	1	12	6	72	8
	Southwind Boulevard	SB	LT	12	6	72	8
Southwind Boulevard		SB	1	6	70	420	47
		SB	1	12	6	72	8
		SB	1	12	10	120	13
		SB	1	12	20	240	27
		SB	1	12	8	96	11
		SB	1	12	6	72	8
		SB	1	12	6	72	8
		SB	1	6	75	450	50
		SB	1	6	75	450	50
		SB	1	6	75	450	50
		SB	1	12	6	72	8
	PCC Pavement	SB	1	12	6	72	8
PCC Pavement		NB	1	12	6	72	8
		NB	1	6	120	720	80
		NB	1	12	30	360	40
		NB	1	12	30	360	40
		NB	1	12	6	72	8
		NB	1	12	6	72	8
		NB	1	12	6	72	8
		NB	1	12	6	72	8
		NB	1	12	6	72	8
		NB	1	12	6	72	8
		NB	1	6	200	1200	133
		NB	1	6	75	450	50
		NB	1	12	6	72	8
		NB	1	12	6	72	8
		NB	1	6	150	900	100
		NB	1	12	6	72	8
		NB	1	12	6	72	8
		NB	1	12	6	72	8
		NB	1	12	6	72	8
		NB	1	12	6	72	8
		NB	1	12	6	72	8
	Bartlett Road	NB	RT	6	100	600	67
						0	0
		TOTALS:			**1194**		**965**
					FT		**SY**

ROUTE: IL 47 (Cross Street to Galena Boulevard)

CROSS STREET FROM	CROSS STREET TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
Galena Boulevard		SB	1	12	6	72	8
		SB	1	12	6	72	8
		SB	1	12	6	72	8
		SB	2	12	6	72	8
	Cross Street	SB	2	12	6	72	8
Cross Street		NB	2	3	100	300	33
		NB	2	12	12	144	16
		NB	2	12	6	72	8
	Galena Boulevard	NB	2	12	6	72	8
		TOTALS:			**154**		**105**
					FT		**SY**

ROUTE: IL 38 (7th Street to 14th Street)

CROSS STREET FROM	CROSS STREET TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
7th Street		WB	1	12	19	228	25
	Richards Street	WB	2	12	19	228	25
Richards Street		WB	1	6	12	72	8
		WB	1	6	100	600	67
		WB	1	3	30	90	10
		WB	2	12	20	240	27
		WB	1	12	20	240	27
		WB	2	3	15	45	5
		WB	1	12	10	120	13
		WB	2	3	15	45	5
		WB	2	12	200	2400	267
		WB	2	3	100	300	33
		WB	2	5	12	60	7
		WB	2	5	12	60	7
		WB	2	3	25	75	8
		WB	2	3	10	30	3
		WB	2	3	15	45	5
		WB	1	3	15	45	5
		WB	2	12	5	60	7
		WB	1	12	5	60	7
		WB	1	12	5	60	7
		WB	2	12	5	60	7
		WB	1	3	10	30	3
		WB	2	3	10	30	3
		WB	2	12	5	60	7
		WB	2	3	6	18	2
		WB	2	3	15	45	5
		WB	2	6	12	72	8
		WB	2	4	12	48	5
	14th Street	WB	1	3	50	150	17
14th Street		EB	2	3	20	60	7
		EB	2	4	12	48	5
		EB	2	3	10	30	3
		EB	2	3	50	150	17
		EB	1	12	4	48	5
		EB	2	12	4	48	5
		EB	2	12	4	48	5
		EB	2	3	50	150	17
		EB	2	12	100	1200	133
		EB	2	12	20	240	27
		EB	1	12	10	120	13
		EB	1	3	25	75	8
	Richards Street	EB	2	3	35	105	12
Richards Street		EB	1	12	19	228	25
	7th Street	EB	2	12	19	228	25
		TOTALS:			**1171**		**931**
					FT		**SY**

1

FILE NAME = c:\pwwork\pwidot\pencepl\d0382486\HMA-Kane.dgn	USER NAME = PencePL	DESIGNED -	REVISED - 1 PLP 05/28/2014	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION
		DRAWN -	REVISED -	
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -	
Default	PLOT DATE = 5/28/2014	DATE -	REVISED -	

INTERMITTENT RESURFACING SCHEDULE
IL 25, IL 47, AND IL 38

SCALE: | SHEET OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2014-024RS	KANE	17	8

CONTRACT NO. 60Y10

ILLINOIS FED. AID PROJECT