ROUTE: IL 173 (Brown Avenue to Deep Lake Road)

CROSS STREET FROM	CROSS STREET TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
200 ft w/o Brown Ave		EB	1	12	3	36	4
		EB	1	12	3	36	4
		EB	1	12	3	36	4
		EB	1	12	3	36	4
		EB	1	12	3	36	4
	CL Brown Ave	EB	1	12	3	36	4
CL Brown Ave		EB	1	12	3	36	4
		EB	1	12	3	36	4
		EB	1	12	3	36	4
		EB	1	12	3	36	4
		EB	1	12	3	36	4
		EB	1	12	3	36	4
		EB	1	12	3	36	4
		EB	1	12	3	36	4
		EB	1	12	3	36	4
		EB	1	12	3	36	4
		EB	2	12	3	36	4
		EB	2	12	3	36	4
		EB	2	12	3	36	4
		EB	2	12	3	36	4
		EB	2	12	3	36	4
		EB	2	12	3	36	4
		EB	2	12	3	36	4
		EB	2	12	3	36	4
		EB	2	12	3	36	4
		EB	2	12	3	36	4
		EB	2	12	3	36	4
		EB	2	12	3	36	4
		EB	2	12	3	36	4
		EB	2	12	3	36	4
		EB	2	12	3	36	4
		EB	2	12	3	36	4
		EB	2	12	3	36	4
		EB	2	12	3	36	4
		EB	1	12	6	72	8
		EB	2	12	6	72	8
		EB	1	12	6	72	8
		EB	2	6	20	120	13
		EB	1	12	30	360	40
		EB	2	6	30	180	20
		EB	2	6	30	180	20
		EB	1/2	40	3	120	13
		EB	1/med	100	3	300	33
		EB	1/med	100	3	300	33
		EB	1/2	100	3	300	33
	CL Deep Lake Rd	EB	1/2	20	3	60	7
CL Deep Lake Rd		EB	1	12	3	36	4
		EB	1	12	3	36	4
		EB	1	12	3	36	4
		EB	1	12	3	36	4
		EB	1	3	20	60	7
		EB	1	3	20	60	7
		EB	1	3	25	75	8
		EB	1	3	35	105	12
	800 ft E/O Deep Lake Rd	EB	1	3	50	150	17

ROUTE: IL 173 (Brown Avenue to Deep Lake Road) (Continued)

CROSS STREET FROM	CROSS STREET TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
800 ft E/O Deep Lake Rd		WB	1	12	3	36	4
		WB	1	12	3	36	4
		WB	1	12	3	36	4
		WB	1	12	3	36	4
		WB	2	12	3	36	4
	CL Deep Lake Rd	WB	2	12	3	36	4
CL Deep Lake Rd		WB	1	12	3	36	4
		WB	1	12	3	36	4
		WB	1	12	3	36	4
		WB	1	12	3	36	4
		WB	2	12	3	36	4
		WB	2	12	3	36	4
		WB	2	12	3	36	4
		WB	1	12	3	36	4
		WB	1	12	3	36	4
		WB	1/2	3	20	60	7
		WB	1/med	3	100	300	33
		WB	1/2	3	200	600	67
		WB	1/med	3	200	600	67
		WB	1/med	3	30	90	10
		WB	1/2	3	50	150	17
		WB	1	12	20	240	27
		WB	1	12	20	240	27
		WB	2	12	20	240	27
		WB	2	12	20	240	27
		WB	2	6	12	72	8
		WB	1	6	100	600	67
		WB	1	6	50	300	33
	CL Brown Ave	WB	1	12	50	600	67
CL Brown Ave		WB	1	12	3	36	4
		WB	1	12	3	36	4
		WB	1	12	3	36	4
		WB	1	12	3	36	4
		WB	1	12	6	72	8
		WB	1	12	20	240	27
		WB	1	12	10	120	13
		WB	1	12	25	300	33
		WB	1	3	30	90	10
		WB	1	3	50	150	17
	200 ft W/O Brown Ave	WB	1	3	70	210	23
		TOTALS:			**1555**		**1112**
					FT		**SY**

FILE NAME = c:\pw_work\pwidot\aumm\d0382486\HMA-Western Lake.dgn	USER NAME = Aumm	DESIGNED -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	DRAWN -	REVISED -
Default	PLOT DATE = 4/4/2014	CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

INTERMITTENT RESURFACING SCHEDULE
IL 173

SCALE: SHEET OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2014-026RS	LAKE	26	7

CONTRACT NO. 60Y12

ILLINOIS FED. AID PROJECT