SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 100% STATE 0005					
	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	37	37					
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	721	721					
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2690	2690					
	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	24015	24015					
	60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	8	8					
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
	67100100	MOBILIZATION	L SUM	1	1					
	70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	3169	3169					
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1056	1056					
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	342	342					
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	33870	33870					
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	985	985					
*	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	50	50					
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	220	220					
	14									

SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 100% STATE 0005					
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	50	50					
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	668	668					
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	668	668					
*	88600600	DETECTOR LOOP REPLACEMENT	FOOT	384	384					
	X4060110	BITUMINOUS MATERIALS (PRIME COAT)	POUND	10807	10807					
	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	360	360					
	9									

* SPECIALTY ITEM

FILE NAME = c:\pw_work\pwidot\pencepl\d0582486\HMA-McHenry.dgn	USER NAME = PencePL	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
Default	PLOT DATE = 4/4/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2014-027RS	MCHENRY	33	3

CONTRACT NO. 60Y13

ILLINOIS FED. AID PROJECT