ROUTE: IL 53 Ramps(Golf Road to Higgins Road)

CROSS STREET FROM	CROSS STREET TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
Golf Road							
SB IL 53		SB	RAMP	12	6	72	8
		SB	RAMP	12	6	72	8
		SB	RAMP	12	6	72	8
		SB	RAMP	12	6	72	8
		SB	RAMP	12	6	72	8
		SB	RAMP	12	6	72	8
		SB	RAMP	12	6	72	8
		SB	RAMP	12	6	72	8
		SB	RAMP	12	10	120	13
		SB	RAMP	12	10	120	13
		SB	RAMP	12	10	120	13
	W. Frontage Road	SB	RAMP	6	8	48	5
Woodfield Road							
SB IL 53		SB	RAMP	16	3	48	5
		SB	RAMP	16	3	48	5
		SB	RAMP	16	3	48	5
		SB	RAMP	16	6	96	11
		SB	RAMP	16	4	64	7
		SB	RAMP	16	6	96	11
		SB	RAMP	12	6	72	8
		SB	RAMP	12	6	72	8
		SB	RAMP	12	6	72	8
		SB	RAMP	12	6	72	8
		SB	RAMP	12	6	72	8
	W. Frontage Road	SB	RAMP	12	6	72	8
Higgins Road							
E. Frontage Road		NB	RAMP	12	6	72	8
		NB	RAMP	12	6	72	8
		NB	RAMP	12	6	72	8
		NB	RAMP	12	6	72	8
	PCC/HMA Jt. NB IL 53 Ramp	NB	RAMP	8	8	64	7
Woodfield Road							
E. Frontage Road		NB	RAMP	3	3	9	1
		NB	RAMP	3	6	18	2
		NB	RAMP	3	10	30	3
		NB	RAMP	12	6	72	8
		NB	RAMP	12	6	72	8
		NB	RAMP	12	6	72	8
		NB	RAMP	12	6	72	8
		NB	RAMP	12	6	72	8
		NB	RAMP	12	6	72	8
	NB IL 53	NB	RAMP	12	6	72	8
Golf Road							
		TOTALS:			**240**		**303**
					FT		**SY**

ROUTE: SB IL 53 (Higgins Road Entrance Ramp)

CROSS STREET FROM	CROSS STREET TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
Higgins Road		SB	1	6	15	90	10
		SB	1,2	3	900	2700	300
		SB	2,3	3	25	75	8
		SB	3	8	20	160	18
		SB	1	12	4	48	5
		SB	1	12	3	36	4
		SB	1	12	3	36	4
		SB	2	18	3	54	6
		SB	1	3	55	165	18
		SB	1	12	3	36	4
		SB	1	3	50	150	17
		SB	1	16	10	160	18
		SB	1	3	60	180	20
		SB	1	12	4	48	5
	PCC/HMA Joint	SB	1	12	6	72	8
		TOTALS:			**1161**		**446**
					FT		**SY**

ROUTE: I-90(Kennedy)(Harlem Avenue to Cicero Avenue NB & SB)

CROSS STREET FROM	CROSS STREET TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
Harlem Avenue		SB	1	12	4	48	5
		SB	1	12	4	48	5
		SB	1	12	6	72	8
		SB	1	12	6	72	8
		SB	1	12	8	96	11
		SB	2	12	4	48	5
		SB	2	12	6	72	8
		SB	2	12	6	72	8
		SB	3	12	4	48	5
		SB	3	12	6	72	8
		SB	3	12	6	72	8
		SB	3	12	8	96	11
	Cicero Avenue	SB	3	12	8	96	11
Cicero Avenue		NB	1	12	8	96	11
		NB	1	12	6	72	8
		NB	1	12	6	72	8
		NB	1	12	6	72	8
		NB	1	12	4	48	5
		NB	2	12	8	96	11
		NB	2	12	6	72	8
		NB	2	12	6	72	8
		NB	2	12	6	72	8
		NB	2	12	6	72	8
		NB	2	12	6	72	8
		NB	3	12	8	96	11
		NB	3	12	6	72	8
		NB	3	12	6	72	8
		NB	3	12	6	72	8
		NB	3	12	6	72	8
		NB	3	12	4	48	5
	Harlem Avenue	NB	3	12	4	48	5
		TOTALS:			**184**		**245**
					FT		**SY**

*COOK, DUPAGE AND LAKE

FILE NAME = c:\pw_work\pwidot\pencepl\d0382486\HMA-Default	USER NAME = PencePL	DESIGNED -	REVISED -
	Expressway-North.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 4/11/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

INTERMITTENT RESURFACING SCHEDULE
IL 53 AND I-90(KENNEDY EXPRESSWAY)

SCALE: | SHEET OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2014-029RS	VARIOUS*	25	14

CONTRACT NO. 60Y15

ILLINOIS FED. AID PROJECT