



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

May 27, 2014

SUBJECT: FAU 1621 (Ridge Road)  
Project M-4003 (314)  
Section 13-00173-00-RS (Lansing)  
Cook County  
Contract No. 61A47  
Item 49  
June 13, 2014 Letting  
Addendum (A)

## NOTICE TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

1. **Sheet 3 of the Plans.**
2. **Special Provisions Table of Contents**
3. **Removed BDE for Hot Mix Asphalt Quality Control for Performance (BMPR) pages 31 thru 34.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John Baranzelli, P.E.  
Acting Engineer of Design and Environment

A handwritten signature in black ink, reading "Ted B. Walschleger P.E." with a stylized flourish at the end.

By: Ted B. Walschleger, P.E.  
Engineer of Project Management

**SPECIAL PROVISIONS  
TABLE OF CONTENTS**

LOCATION OF PROJECT ..... 3

DESCRIPTION OF PROJECT ..... 3

TRAFFIC CONTROL PLAN ..... 3

MAINTENANCE OF ROADWAYS ..... 4

STATUS OF UTILITIES TO BE ADJUSTED ..... 4

SAW CUT JOINTS ..... 5

COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT ..... 5

SODDING, SALT TOLERANT (SPECIAL) ..... 6

DETECTABLE WARNINGS ..... 6

HOT-MIX ASPHALT SHOULDERS, 8" ..... 6

TRAFFIC SIGNAL SPECIFICATIONS FOR DETECTOR REPLACEMENT AND/OR INSTALLATION ON ROADWAY GRINDING,  
RESURFACING, & PATCHING OPERATIONS ..... 7

HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 4" ..... 10

FRAME AND ADJUSTING RING SEALS ..... 10

FINE AGGREGATE FOR HOT-MIX ASPHALT (HMA) (D-1) ..... 10

FRICTION SURFACE AGGREGATE (D1) ..... 10

HOT MIX ASPHALT MIXTURE IL-4.75 (DIST 1) ..... 13

RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES (D-1) ..... 15

GROUND TIRE RUBBER (GTR) MODIFIED ASPHALT BINDER (D-1) ..... 24

HOT MIX ASPHALT MIXTURES, EGA MODIFIED PERFORMANCE GRADED (PG) ASPHALT BINDER ..... 25

HMA MIXTURE DESIGN REQUIREMENTS (D-1) ..... 26

~~HOT MIX ASPHALT QUALITY CONTROL FOR PERFORMANCE (BMPR) ..... 31~~

HOT-MIX ASPHALT – PRIME COAT (D-1) ..... 34

DRAINAGE AND INLET PROTECTION UNDER TRAFFIC (DISTRICT 1) ..... 38

ADJUSTMENTS AND RECONSTRUCTIONS ..... 39

△  
5-20-2014

Revised 5/27/14

No additional compensation will be awarded to the Contractor because of reduced production rates associated with the addition of the anti-stripping additive."

**HOT MIX ASPHALT QUALITY CONTROL FOR PERFORMANCE (BMPR)**

Effective: January 1, 2012  
 Revised: December 1, 2013

Description. This special provision describes the procedures for production, placement and payment of hot-mix asphalt (HMA). This work shall be according to the Standard Specifications except as modified herein. This special provision shall apply to HMA mixtures as listed in the following table.

Mixture/Use:	Hot-Mix Asphalt Surface Course, Mix D, N50
Location:	Roadway Surface Course
Mixture/Use:	
Location:	
Mixture/Use:	
Location:	

Exceptions may be approved for small tonnage less than 800 (725 metric) tons and miscellaneous mixture applications as defined by the Engineer.

- Delete Articles: 406.06(b)(1), 2<sup>nd</sup> Paragraph (Temperature requirements)  
 406.06 (e), 3<sup>rd</sup> Paragraph (Pavers speed requirements)  
 406.07 (Compaction)  
 1030.05(a)(4, 5, 9,) (QC/QA Documents)  
 1030.05(d)(2)a. (Plant Tests)  
 1030.05(d)(2)b. (Dust-to-Asphalt and Moisture Content)  
 1030.05(d)(2)d. (Small Tonnage)  
 1030.05(d)(2)f. (HMA Sampling)  
 1030.05(d)(3) (Required Field Tests)  
 1030.05(d)(4) (Control Limits)  
 1030.05(d)(5) (Control Charts)  
 1030.05(d)(7) (Corrective Action for Field Tests (Density))  
 1030.05(e) (Quality Assurance by the Engineer)  
 1030.05(f) (Acceptance by the Engineer)  
 1030.06(a), 3<sup>rd</sup> paragraph (Before start-up...)  
 1030.06(a), 7<sup>th</sup> paragraph (After an acceptable...)  
 1030.06(a), 8<sup>th</sup> paragraph (If a mixture...)  
 1030.06(a), 9<sup>th</sup> paragraph (A nuclear/core...)

Definitions:

Deleted 5/27/14

- (a) Quality Control (QC): All production and construction activities by the Contractor required to achieve the required level of quality.
- (b) Quality Assurance (QA): All monitoring and testing activities by the Engineer required to assess product quality, level of payment, and acceptability of the product.
- (c) Pay Parameters: Pay Parameters shall be field Voids in the Mineral Aggregate (VMA), voids, and density. Field VMA will be calculated using the combined aggregates bulk specific gravity ( $G_{sb}$ ) from the mix design.
- (d) Mixture Lot. A lot shall begin once an acceptable test strip has been completed and the AJMF has been determined. If the test strip is waived, a subplot shall begin with the start of production. A mixture lot shall consist of four sublots unless it is the last or only lot, in which case it may consist of as few as one subplot
- (e) Mixture Sublot. A mixture subplot for field VMA, voids, and Dust/AC will be a maximum of 1000 tons (910 metric tons).
- If the remaining quantity is greater than 200 but less than 1000 tons, a subplot will consist of that amount.
  - If the remaining quantity is less than or equal to 200 tons, the quantity shall be combined with the previous subplot.
- (f) Density Interval. Density Intervals shall be every 0.2 mile (320 m) for lift thickness equal to or less than 3 in. (75 mm) and 0.1 mile (160 m) for lift thickness greater than 3 in. (75 mm).
- (g) Density Sublot. A subplot for density shall be the average of five consecutive Density Intervals. If a Density Interval is less than 200 ft (60 m), it will be combined with the previous Density Intervals.
- If one or two Density Intervals remain outside a subplot, they shall be included in the previous subplot.
  - If three or more Density Intervals remain, they shall be considered a subplot.
- (h) Density Test: A density test consists of a core taken at a random longitudinal and random transverse offset within each Density Interval. The HMA maximum theoretical gravity ( $G_{mm}$ ) will be based on the running average of four Department test results. Initial  $G_{mm}$  will be based on the average of the first four test results. If less than four  $G_{mm}$  results are available, use an average of all available Department  $G_{mm}$  test results.

The random transverse offset excludes a distance from each outer edge equal to the lift thickness or a minimum of 4 in. (100 mm). If a core is located within one foot of an unconfined edge, 2.0 percent density will be added to the density of that core.

Quality Control (QC) by the Contractor:

The Contractor's QC plan shall include the schedule of testing for both pay parameters and non-pay parameters required to control the product such as asphalt binder content and mixture gradation. The minimum test frequency shall be according to the following table.

Minimum Quality Control Sampling and Testing Requirements

Quality Characteristic		Minimum Test Frequency
Mixture Gradation		1 per subplot
Asphalt Binder Content		
Dust/AC Ratio		
Field VMA		
Voids	G <sub>mb</sub>	
	G <sub>mm</sub>	

The Contractor's splits in conjunction with other quality control tests shall be used to control production.

The Contractor shall submit split jobsite mix sample test results to the Engineer within 48 hours of the time of sampling. All QC testing shall be performed in a qualified laboratory by personnel who have successfully completed the Department's HMA Level I training.

Quality Assurance (QA) by the Engineer:

Voids, field VMA and Dust/AC ratio: The Engineer will determine the random tonnage and the Contractor shall be responsible for obtaining the sample according to the "PFP Hot-Mix Asphalt Random Jobsite Sampling" procedure.

Density: The Engineer will identify the random locations for each density testing interval. The Contractor shall be responsible for obtaining the four inch cores within the same day and prior to opening to traffic unless otherwise approved by the Engineer according to the "PFP and QCP Random Density Procedure". The locations will be identified after final rolling and cores shall be obtained under the supervision of the Engineer. All core holes shall be filled immediately upon completion of coring. All water shall be removed from the core holes prior to filling. All core holes shall be filled with a rapid hardening mortar or concrete which shall be mixed in a separate container prior to placement in the hole. Any depressions in the surface of the filled core holes greater than 1/4 inch at the time of final inspection will require removal of the fill material to the depth of the lift thickness and replacement.

The Engineer will witness and secure all mixture and density samples. The Contractor shall transport the secured sample to a location designated by the Engineer.

The Engineer will test one or all of the randomly selected split samples from each lot for Voids, field VMA and dust/AC ratio. The Engineer will test a minimum of one sample per project. The Engineer will test all of the pavement cores for density. All QA testing will be performed in a qualified laboratory by personnel who have successfully completed the Department's HMA Level I training. QA test results will be available to the Contractor within 10 working days from receipt of secured cores and split mixture samples.

The Engineer will maintain a complete record of all Department test results and copies will be provided to the Contractor with each set of subplot results. The records will contain, as a minimum, the originals of all Department test results and raw data, random numbers used and resulting calculations for sampling locations, and quality level analysis calculations.

If the QA results do not meet the 100% subplot pay factor limits or do not compare to QC results within the precision limits listed below, the Engineer will test all split mix samples for the lot.

Deleted 5/27/14

Ridge Road  
 Section: 13-00173-00-RS  
 Village of Lansing  
 Contract No.: 61A47  
 County: Cook

Test Parameter	Limits of Precision
G <sub>mb</sub>	0.030
G <sub>mm</sub>	0.026
Field VMA	1.0 %

Acceptance by the Engineer: All of the Department's tests shall be within the acceptable limits listed below:

Parameter	Acceptable Limits
Field VMA	-1.0 - +3.0% <sup>1/</sup>
Voids	2.0 - 6.0%
Density:	IL-9.5, IL-12.5, IL-19.0, IL-25.0, IL-4.75, IL-9.5FG <sup>3/</sup>
	SMA
Dust / AC Ratio	0.4 - 1.6 <sup>2/</sup>

- 1/ Based on minimum required VMA from mix design
- 2/ Does not apply to SMA.
- 3/ Acceptable density limits for IL-9.5FG placed less than 1.25 in. shall be 89.0% - 98.0%

In addition, no visible pavement distresses shall be present such as, but not limited to, segregation, excessive coarse aggregate fracturing or flushing.

Basis of Payment: Payment will be based on the calculation of the Composite Pay Factor using QA results for each mix according to the "QCP Payment Calculation" document.

Dust / AC Ratio. A monetary deduction will be made using the pay adjustment table below for dust/AC ratios that deviate from the 0.6 to 1.2 range. If the tested subplot is outside of this range, the Department will test the remaining sublots for Dust / AC pay adjustment.

Dust / AC Pay Adjustment Table<sup>1/</sup>

Range	Deduct / subplot
$0.6 \leq X \leq 1.2$	\$0
$0.5 \leq X < 0.6$ or $1.2 < X \leq 1.4$	\$1000
$0.4 \leq X < 0.5$ or $1.4 < X \leq 1.6$	\$3000
$X < 0.4$ or $X > 1.6$	Shall be removed and replaced

1/ Does not apply to SMA.

HOT-MIX ASPHALT - PRIME COAT (D-1)

5-20-2014

Effective: February 19, 2013  
 Revised: April 1, 2014

Revise Note 1 of Article 406.02 of the Standard Specifications to read:

Revised 5/27/14