

SUMMARY OF QUANTITIES

| CODE #     | ITEM                                            | UNIT   | TOTAL QUANTITY | URBAN                              |                                  |
|------------|-------------------------------------------------|--------|----------------|------------------------------------|----------------------------------|
|            |                                                 |        |                | ROCK ISLAND 90% FED 10% STATE 0005 | WHITESIDE 90% FED 10% STATE 0005 |
| 70100420   | TRAFFIC CONTROL AND PROTECTION, STANDARD 701411 | EACH   | 22             | 22                                 | 0                                |
| 70100700   | TRAFFIC CONTROL AND PROTECTION, STANDARD 701406 | L SUM  | 1              | 1                                  | 0                                |
| 70100800   | TRAFFIC CONTROL AND PROTECTION, STANDARD 701401 | L SUM  | 1              | 1                                  | 0                                |
| 70100820   | TRAFFIC CONTROL AND PROTECTION, STANDARD 701451 | L SUM  | 1              | 1                                  | 0                                |
| 70100825   | TRAFFIC CONTROL AND PROTECTION, STANDARD 701456 | L SUM  | 1              | 1                                  | 0                                |
| 70103815   | TRAFFIC CONTROL SURVEILLANCE                    | CAL DA | 40             | 40                                 | 0                                |
| 70300100   | SHORT TERM PAVEMENT MARKING                     | FOOT   | 147,630        | 144,723                            | 2907                             |
| 70301000   | WORK ZONE PAVEMENT MARKING REMOVAL              | SQ FT  | 16,403         | 16,080                             | 323                              |
| 72700100   | STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY       | POUND  | 440            | 440                                | 0                                |
| 73400100   | CONCRETE FOUNDATIONS                            | CU YD  | 1.4            | 1.4                                | 0                                |
| * 78009004 | MODIFIED URETHANE PAVEMENT MARKING - LINE 4"    | FOOT   | 350,683        | 344,855                            | 5828                             |
| * 78009006 | MODIFIED URETHANE PAVEMENT MARKING - LINE 6"    | FOOT   | 37,846         | 37,117                             | 729                              |
| * 78009008 | MODIFIED URETHANE PAVEMENT MARKING - LINE 8"    | FOOT   | 11,040         | 11,040                             | 0                                |
| * 78009012 | MODIFIED URETHANE PAVEMENT MARKING - LINE 12"   | FOOT   | 1,608          | 1,608                              | 0                                |
| * 78100100 | RAISED REFLECTIVE PAVEMENT MARKER               | EACH   | 2,472          | 2,436                              | 36                               |
| * 78200410 | GUARDRAIL MARKERS, TYPE A                       | EACH   | 10             | 8                                  | 2                                |
| * 78200520 | BARRIER WALL MARKERS, TYPE B                    | EACH   | 37             | 37                                 | 0                                |
| * 78201000 | TERMINAL MARKER - DIRECT APPLIED                | EACH   | 11             | 10                                 | 1                                |

| CODE #                | ITEM                                                                      | UNIT             | TOTAL QUANTITY   | URBAN                              |                                  |
|-----------------------|---------------------------------------------------------------------------|------------------|------------------|------------------------------------|----------------------------------|
|                       |                                                                           |                  |                  | ROCK ISLAND 90% FED 10% STATE 0005 | WHITESIDE 90% FED 10% STATE 0005 |
| 78300200              | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL                                 | EACH             | 2,472            | 2,436                              | 36                               |
| Ⓢ X0320882            | GUTTERS TO BE CLEANED                                                     | FOOT             | 1,119            | 1,119                              | 0                                |
| X0323388              | TRAFFIC COUNTER                                                           | EACH             | 1                | 1                                  | 0                                |
| X0325088              | PLACEMENT OF CEMENT GROUT                                                 | CU FT            | 40               | 40                                 | 0                                |
| X0326401              | BARRIER WALL REMOVAL                                                      | FOOT             | 185              | 185                                | 0                                |
| X4060115              | POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)                             | POUND            | 830,391          | 816,879                            | 13512                            |
| X4401198              | HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH                           | SQ YD            | 8,820            | 8,820                              | 0                                |
| X6062400              | CONCRETE GUTTER (SPECIAL)                                                 | FOOT             | 80               | 80                                 | 0                                |
| X6333500              | TRAFFIC BARRIER TERMINAL REMOVAL                                          | EACH             | 8                | 7                                  | 1                                |
| X7010410              | SPEED DISPLAY TRAILER                                                     | CAL MO           | 10               | 8                                  | 2                                |
| * X7830070            | GROOVING FOR RECESSED PAVEMENT MARKING 5"                                 | FOOT             | 350,583          | 344,755                            | 5828                             |
| * X7830074            | GROOVING FOR RECESSED PAVEMENT MARKING 7"                                 | FOOT             | 37,844           | 37,115                             | 729                              |
| * X7830076            | GROOVING FOR RECESSED PAVEMENT MARKING 9"                                 | FOOT             | 11,040           | 11,040                             | 0                                |
| * X7830078            | GROOVING FOR RECESSED PAVEMENT MARKING 13"                                | FOOT             | 1,608            | 1,608                              | 0                                |
| * <del>Z0004004</del> | <del>JACK AND REPOSITION BEARINGS</del>                                   | <del>EACH</del>  | <del>9</del>     | <del>9</del>                       | <del>0</del>                     |
| * Z0008758            | AERIAL SPEED CHECK MARKING                                                | FOOT             | 72               | 72                                 | 0                                |
| * <del>Z0012754</del> | <del>STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 6")</del> | <del>SQ FT</del> | <del>1,484</del> | <del>1,484</del>                   | <del>0</del>                     |
| Z0028415              | GEOTECHNICAL REINFORCEMENT                                                | SQ YD            | 425              | 425                                | 0                                |
| Z0034105              | MATERIAL TRANSFER DEVICE                                                  | TON              | 93,929           | 92,423                             | 1,506                            |
| * Z0053200            | REPAIR TRAFFIC BARRIER TERMINAL, TYPE 6                                   | EACH             | 1                | 0                                  | 1                                |

Ⓢ Z0076000 TRAINEES HOUR 2000 2000  
Ⓢ Z0076004 TRAINEES - TRAINING PROGRAM GRADUATE HOUR 2000 2000  
Ⓢ 100% STATE (NP)  
Ⓢ 0042