

SUMMARY OF QUANTITIES

URBAN
0014
100%
STATE

CODE NUMBER	ITEM	UNIT	100% STATE TOTAL QUANTITY	100% STATE WHITESIDE COUNTY
50102400	CONCRETE REMOVAL	CU YD	12.9	12.9
50300255	CONCRETE SUPERSTRUCTURE	CU YD	13.0	13.0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,800	1,800
50800515	BAR SPLICERS	EACH	32	32
50800530	MECHANICAL SPLICERS	EACH	60	60
52000110	PREFORMED JOINT STRIP SEAL	FOOT	170	170
52000212	FINGER PLATE EXPANSION JOINT, 4"	FOOT	30	30
52000600	FABRIC REINFORCED ELASTOMERIC TROUGH	FOOT	42	42
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3
67100100	MOBILIZATION	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	3	3
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	356.5	356.5
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	374.4	374.4
Z0073200	TEMPORARY SHORING AND CRIBBING	EACH	5	5
Z0031200	JACKING AND CRIBBING	EACH	5	5

Rev