

INDEX OF SHEETS

- 1 COVER PAGE
- 2 INDEX OF SHEETS, GENERAL NOTED, STATE STANDARDS, DISTRICT STANDARDS
- 3 SUMMARY OF QUANTITIES
- 4 DISTRICT STANDARDS
- 5 EXISTING TYPICAL SECTIONS
- 6 TYPICAL SECTION STAGING
- 7 - 9 PLAN SHEETS
- 10 - 12 ISLAND REMOVAL PLAN SHEETS
- 13 - 15 TEMPORARY PAVEMENT PLAN SHEETS
- 16 - 21 TRAFFIC CONTROL PLAN
- * 22 - 35 EXISTING BRIDGE PLANS
28-35 DELETED

STATE STANDARDS

- 606001 - 05 CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
- 701001 - 02 OFF-ROAD OPERATIONS, 2L, 2W, MORE THAN 15' (4.5 m) AWAY
- 701006 - 05 OFF-ROAD OPERATIONS, 2L, 2W, 15' (4.5 m) TO 24" (600 mm) FROM PAVEMENT EDGE
- 701101 - 04 OFF-RD OPERATIONS, MULTILANE, 15' (4.5 m) TO 24" (600 mm) FROM PAVEMENT EDGE
- 701201 - 04 LANE CLOSURE 2L, 2W, DAY ONLY, FOR SPEEDS ≥ 45 MPH
- 701301 - 04 LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
- 701311 - 03 LANE CLOSURE 2L, 2W MOVING OPERATIONS-DAY ONLY
- 701321 - 13 LANE CLOSURE, 2L, 2W, BRIDGE REPAIR WITH BARRIER
- 701331 - 04 LANE CLOSURE, 2L, 2W, WITH RUN-AROUND, FOR SPEEDS 45 MPH
- 701502 - 06 URBAN LANE CLOSURE, 2L, 2W, BI-DIRECTIONAL LEFT TURN LANE
- 701701 - 09 URBAN LANE CLOSURE MULTILANE INTERSECTION
- 701901 - 03 TRAFFIC CONTROL DEVICES
- 704001 - 07 TEMPORARY CONCRETE BARRIER
- 720011 - 01 METAL POSTS FOR SIGNS, MARKERS & DELINEATORS
- 728001 - 01 TELESCOPING STEEL SIGN SUPPORT
- 729001 - 01 APPLICATIONS OF TYPES A & B METAL POSTS (FOR SIGNS & MARKERS)

DISTRICT STANDARDS

39.2 INFORMATIONAL WARNING SIGNS (FOR NARROW TRAVEL LANES)

GENERAL NOTES

ALL BORROWWASTEUSE SITES MUST BE APPROVED BY THE DEPARTMENT PRIOR TO REMOVING ANY MATERIAL FROM THE PROJECT OR INITIATING ANY EARTHMOVING ACTIVITIES, INCLUDING TEMPORARY STOCKPIILING OUTSIDE THE LIMITS OF CONSTRUCTION.

THE CONTRACTOR SHALL SEED ALL DISTURBED AREAS WITHIN THE PROJECT LIMITS. SEEDING 2A SHALL BE USED. THIS WORK WILL BE INCLUDED IN THE CONTRACT UNIT PRICE PER LUMP SUM FOR CLEANING AND PAINTING STEEL BRIDGE NO.1 AND CLEANING AND PAINTING STEEL BRIDGE NO.2 RESPECTIVELY.

MULCH METHOD II SHALL BE APPLIED OVER ALL SEEDED AREAS. THIS SHALL BE INCLUDED IN THE COST OF THE CLEANING AND PAINTING STEEL BRIDGE NO.1 AND CLEANING AND PAINTING STEEL BRIDGE NO.2 RESPECTIVELY.

FERTILIZER NUTRIENTS SHALL BE APPLIED AT THE RATE SPECIFIED IN SECTIONS 250 AND 252 OF THE STANDARD SPECIFICATIONS. THIS SHALL BE INCLUDED IN THE COST OF THE CLEANING AND PAINTING STEEL BRIDGE NO.1 AND CLEANING AND PAINTING STEEL BRIDGE NO.2 RESPECTIVELY.

THE SSPC OP1 AND OP2 CONTRACT CERTIFICATIONS WILL BE REQUIRED FOR THIS CONTRACT.

NO MATERIALS, EQUIPMENT, VEHICLES OR OTHER HAZARDS SHALL BE WITHIN 3'-6" OF THE TEMPORARY CONCRETE BARRIER WALL MEASURED FROM THE CLOSEST POINT OF THE BARRIER WALL PERPENDICULAR TO THE HAZARD. BARRIER WALL SHAL BE PINNED ON THE TRAFFIC SIDE OF THE BARRIER WALL STA. 99+15 TO STA. 99+65 & FROM STA. 100+30 TO STA. 100+88.

NOTHING SHALL BE STORED WITHIN 25 FT OF IMPACT ATTENUATORS & WITHIN 25 FT OF HINGE POINT OF BARRIER WALL

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY DURING CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. A MINIMUM OF 48 HOURS ADVANCE NOTICE IS REQUIRED FOR NON-EMERGENCY WORK. THE JULIE NUMBER IS 800-892-0123. THE FOLLOWING LISTED UTILITIES LOCATED WITHIN THE PROJECT LIMITS OR IMMEDIATELY ADJACENT TO THE PROJECT CONSTRUCTION LIMITS ARE MEMBERS OF JULIE:

Company	Type	Contact Name	Contact Information
Commonwealth Edison Company	Electric	Ms. Nora Fernandez	123 Energy Ave. Rockford, IL 61109 Phone No. 815-490-2889
Fronter	Telephone	Mr. Donald Bolnera	2239 Newburg Road, Belvidere IL 61008 Phone No. 815-644-8171
Windstream	Telephone	Mr. Paul Boumann	1815 S. Mayores Road, Suite 900 Oak Brooke Terrace IL 60181 Phone No. 630-825-4751
G4S Technology, LLC	Communications	Mr. Chance Elker	1428 Sherman Road, Romeoville IL 60446 Phone No. 630-343-2802

IDOT IS NOT A MEMBER OF JULIE. IF YOU ARE NEAR ANY OVERHEAD LIGHTING, INTERSECTION LIGHTING OR TRAFFIC SIGNALS, CONTACT THE IDOT TRAFFIC OFFICE AT 815/284-5469 AT LEAST 48 HOURS PRIOR TO WORK.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO CONTACT THE MUNICIPALITY TO DETERMINE APPROVED METHODS OF UTILITY STRUCTURE ADJUSTMENT. UTILITY STRUCTURES MAY INCLUDE, BUT ARE NOT LIMITED TO, MANHOLES, WATER VALVES, HANDHOLES, ETC. ALL MATERIALS AND WORK NECESSARY TO COMPLETE ADJUSTMENTS PER MUNICIPALITY REQUIREMENTS SHALL BE CONSIDERED INCLUDED IN THE COST OF THE ASSOCIATED ADJUSTMENT PAY ITEM.

DESIGNED - _____	REVISED - _____	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, GENERAL NOTES STATE STANDARDS, DISTRICT STANDARDS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
				39	02 Bridge Painting 2014-3	LEE	35	2
DRAWN - _____	REVISED - _____			SHEET _____ OF _____ SHEETS		STA. _____ TO STA. _____	[ILLINOIS] FED. AID PROJECT	
CHECKED - _____	REVISED - _____						CONTRACT NO. 64K10	
DATE - _____	REVISED - _____						Rev.	