

SUMMARY OF QUANTITIES			100% State 0014
Pay Item No.	Description	Units	Total Quantity
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2,338
60608562	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.12	FOOT	2,338
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	8,215
67100100	MOBILIZATION	L SUM	1
70100200	TRAFFIC CONTROL AND PROTECTION, STANDARD 701331	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	170
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	187.2
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	10,968
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,040
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	480
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4,484
70400100	TEMPORARY CONCRETE BARRIER	FOOT	646.17
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	646.17
70600250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2
70600350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	10,400
78300100	PAVEMENT MARKING REMOVAL	SQ FT	800
X4400110	TEMPORARY PAVEMENT REMOVAL	SQ YD	1,303
X4403800	MEDIAN SURFACE REMOVAL	SQ FT	8,215
X5067501	BRIDGE CLEANING AND PAINTING WARRANTY NUMBER 1	L SUM	1
X5067502	BRIDGE CLEANING AND PAINTING WARRANTY NUMBER 2	L SUM	1
Z0007101	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 1	L SUM	1
Z0007102	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 2	L SUM	1
Z0010501	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1
Z0010502	CLEANING AND PAINTING STEEL BRIDGE NO. 2	L SUM	1
Z0062456	TEMPORARY PAVEMENT	SQ YD	1,303

29

* Specialty Items

DESIGNED - _____	REVISED - _____	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
DRAWN - _____	REVISED - _____			39	D2 Bridge Painting 2014-3	LEE	35	3
CHECKED - _____	REVISED - _____			CONTRACT NO. 64K10				
DATE - _____	REVISED - _____			ILLINOIS FED. AID PROJECT				
				SHEET _____ OF _____ SHEETS		STA. _____ TO STA. _____		